







Stainless Solid

Integrated Solid

## **Key Features**

- Daily ice production of up to 39 lb of ice
- Up to 23 lb in ice storage capacity
- Clear ice cube dimensions: 3/4" W x 3/4" H x 3/4" L
- Silent setting temporarily suspends ice making for 3 hours
- Digital Touch Pad Control
- Indicator alert notifies user when cleaning is needed
- Black interior
- Bright white LED lighting

- Clear heavy duty ice scoop included
- Drain required
- Factory installed drain pump
- Stainless steel handle (1/8" diameter)
- Field reversible door is shipped right-hand hinged
- Built-in or freestanding
- Four adjustable leveling legs

## **Model Details**


Model	Voltage/Hz	Door Swing	Pump	Finish	Shipping Weight
UACP115-SS01A	115 / 60	Field Reversible	Pump Included	Stainless Solid	125 lb
UACP115-IS01A	115 / 60	Field Reversible	Pump Included	Integrated Solid	125 lb

## **Accessories**

Model	Description	Finish	Shipping Weight
80-55667-00	Clear Ice Machine Cleaner	N/A	1 lb
ULAWATERHOOKUP	Braided Water Supply Line Kit	N/A	2 lb


Front

Dimensions shown apply to all finishes, including Integrated (INT) models with  $\frac{3}{4}$ " integrated panel/frame installed.



#### Side


# Тор




# **Specifications**

Model	ACP115	
Amps: Running	3.0	
Amps: Ice Harvest	3.5	
Control Type	Digital Touch Pad	
Defrost Type	N/A	
Dimensions: Product Depth	23 5/8"	
Dimensions: Product Height	31 1/8"	
Dimensions: Product Width	14 7/8"	
ENERGY STAR	N/A	
Ice Production Per Day	39 lb	
Ice Storage	23 lb	
Panel Height	27 ½32" / 687mm	
Panel Thickness	<sup>3</sup> / <sub>4</sub> " / 20 mm	
Panel Type	Solid Panel	
Panel Width	14 %" / 371mm	
Product Weight: Max	125 lb	
Refrigerant Type	R600a (1.94 oz)	
Sabbath (Star K Certified)	Yes	

#### Duck



## **Cabinet Cut-Out**



# Warranty

- 1 Year (parts & labor) / 5 year sealed system (parts)
- Additional 1 Year (parts & labor) warranty at no cost with product registration

See complete warranty for details



#### **Installation Notes**

- No additional clearance is needed for ventilation
- Do not obstruct front grille air flow





