

Pre-Terminated Overhead Distribution Domes



Product Description

Overhead distribution domes are pre-terminated, therefore have all quality control checks performed prior to deployment in the access network. This is a reliable solution

The Dome Closure is moisture resistant and Modular connectors are fitted inside the terminal unit providing a cost effective solution in populating the subscriber terminal boxes to whatever pair count is required rather than pre-tailed terminal blocks. The drop wire modular connector system incorporates both over voltage and over current capabilities as well as providing remote test access

The pre-terminated cables can also be installed in Cabinets, therefore minimizing installation times.

Applications

- Overhead / Underground access networks on poles, cabinets, underground pits

DexGreen Ltd, Unit 2, Pinnacle Business Park, Ballytrasna, Little Island, Co. Cork, Ireland

Tel: +353 21 4317955

Email: sales@dexgreen.com

Fax: +353 21 4316269

Internet: www.dexgreen.com



Certification
number: 21216