





LG-150 CORNER GUARD AT FULL HEIGHT ELEVATION

## LG-150

|   | SPECIFIED FASTENER   | DRILL DIAMETERS |          | CS PART                |
|---|--|-----------------|----------|------------------------|
| WALL CONDITION  |  | DRIEL DIAWLTERS |          |                        |
|   |  | WALL            | RETAINER | NUMBER                 |
| STEEL STUD/GYPSUM WALL<br>WOOD STUD/GYPSUM WALL<br>CONCRETE/CONC. BLOCK | LG 034 1 1/8" SCREW/NAIL<br>LG 118/150/200/250 1" SCREW NAIL | N/A             | N/A      | 90H136002<br>90H135002 |

NOTE: LG CORNER GUARDS THAT ARE REQUESTED WITHOUT PRE-DRILLED HOLES DO NOT INCLUDE FASTENERS WITH THE EXCEPTION OF MODEL LG-034. FOR MODEL LG-034, FASTENERS ARE ALWAYS SUPPLIED, AND HOLES ARE NOT PRE-DRILLED.



Hughesville, PA | 800.233.8493 | 570.546.5941 Mississauga, ON | 888.895.8955 | 905.274.3611 www.c-sgroup.com

© Copyright 2017 Construction Specialties, Inc.

| PROJECT:  | REVISION: |
|-----------|-----------|
| JOB NO.:  | F&F:      |
| CUSTOMER: |           |
| REP:      | DATE:     |
| DRAWN BY: | SHEET NO: |

DOC#: TS-930-218 ISSUE DATE: 11/10/00 REV DATE: 8/4/17