



M TILE PROGRAM



INSPECTING YOUR SHIPMENT

PLEASE NOTE THAT MARBLE IS A NATURAL MATERIAL AND AS SUCH, IS SUBJECT TO NATURAL VARIATIONS IN COLOR, VEINING AND SPOTTING. OUR TILES ARE CUT FROM LARGE BLOCKS OF STONE AND WILL THEREFORE EXHIBIT VARIATION IN COLOR AND SHADE ACROSS PRODUCTION LOTS OR BATCHES DEPENDING ON THE AREA OF THE SLAB THAT A LOT WAS PULLED FROM. WITH THAT SAID, THE SAMPLE YOU RECEIVED MAY NOT BE A PERFECT MATCH WITH YOUR ACTUAL ORDER. PLEASE BE AWARE THAT INSTALLATION IS CONSIDERED AS ACCEPTANCE OF MATERIALS. WITH THAT SAID, IF YOU ARE HAVING ANY CONCERNS REGARDING YOUR ORDER, PLEASE REACH OUT PRIOR TO INSTALLATION.



INSTALLATION

TO ENSURE PROPER INSTALLATION, PLEASE MAKE SURE YOU HAVE SELECTED AN INSTALLER WITH PROPER EXPERIENCE. ANY MISUSE OF THE TILES INCLUDING CARELESS, PHYSICAL AND/OR CHEMICAL ABUSE IS NOT COVERED BY MLL WARRANTY.

INSTALLATION AREAS

MARBLE TILES CAN BE USED ON INTERIOR FLOORS, FIREPLACE SURROUNDS THAT ARE RADIANT HEATING COMPATIBLE. MARBLE TILES CAN BE INSTALLED ON BACKSPLASHES, BATHROOMS, SHOWERS AND STEAM SHOWERS WITH APPLICATION OF A WATERPROOFING, PENETRATING SEALANT. MARBLE TILES CAN BE USED AS A STOVE BACKSPLASH WITH ADDITIONAL PLACEMENT ISSUES TAKEN INTO CONSIDERATION. MARBLE TILES ARE NOT SUITABLE FOR POOL AND FOUNTAIN WATER LINES. MARBLE TILES ARE NOT FREEZE/THAW RESISTANT.



MAINTANENCE & CARE

ROUTINE, DAILY MAINTENANCE OF MARBLE SURFACES WILL INVOLVE KEEPING DIRT, DUST AND OTHER SOILING FROM BUILDING UP. ANY POTENTIAL STAINING MUST BE CLEANED UP IN A REASONABLE PERIOD OF TIME TO AVOID PERMANENT STAINING. REGULAR SWEEPING AND LIGHT DAMP MOPPING IS RECOMMENDED. HIGHLY ALKALINE, ACIDIC, AMMONIA BASED, ABRASIVE CLEANERS, OR BLEACH MAY DAMAGE THE TILE. THE USE OF A GENTLE CLEANER SPECIFICALLY FORMULATED FOR MARBLE TILE IS RECOMMENDED.

TILE SIZE & DEPTH

PLEASE NOTE THERE IS A 1MM TOLERANCE ON ALL STONE TILES.

4" X 4" THICKNESS IN 3/8"

8" X 4" THICKNESS IN 3/5"

12" X 12" THICKNESS IN 3/5"

24" X 24" THICKNESS IN 3/5"



SHIPPING & DELIVERY TIMELINE

SHIPPING PRICING TO BE QUOTED BASED ON ORDER QUANTITY AND LOCATION. PLEASE ALLOW 12 - 14 WEEKS FOR DELIVERY. PLEASE NOTE THAT TIMELINE MAY FLUCTUATE BASED ON ORDER QUANTITY.

MINIMUM ORDER QUANTITY

150 SQ. FT. IS THE MINIMUM ORDER QUANTITY. PLEASE NOTE THAT WE RECOMMEND ADDING A 20% OVERAGE DUE TO POTENTIAL BREAKAGE, EXTRA TILES NEEDED FOR CUTTING, OR FUTURE REPAIRS.



AVAILABLE STONES

