SATCO NUVO

Project Name

Location

Prepared By



NUVO 65-760

LED CUTOFF WALL PACK CCT&WATT

Notes

www] 03-22-2021 04:50:5

| General | | |
|---------------------------|--------------------|--|
| Status | Active | |
| Fixture Type | Wall Pack | |
| Finish | Bronze | |
| Wattage | 29W/40W/60W | |
| Lumen Output | 3915-8400 | |
| CCT (Kelvin) | 3000K/4000K/5000K | |
| IP Rating | IP65 | |
| Indoor or Outdoor Fixture | Indoor and Outdoor | |

| Specifications | | |
|-----------------------|---------------------------------------|--|
| Technology | LED | |
| CRI | >80 | |
| Voltage | 120V-277V | |
| Beam Angle | 110 | |
| Rated Hours | 50000 | |
| Operating Temperature | -40C (-40F) to a maximum of 50C (122) | |
| Dimmable | Yes - Dimmable | |
| Photocell | Yes - bypassable | |
| Lens Material | Glass/PC | |
| Weight (lb.) | 10.5 | |
| Material | Die-Cast Aluminum | |

| Dimensions | |
|-----------------|-------|
| Height (in.) | 9.83 |
| Width (in.) | 14.26 |
| Extension (in.) | 9.33 |

| Compliance | |
|--------------------|--------------------------|
| Safety Listing | cULus Certified |
| Location Rating | Wet |
| DLC Approved | Yes |
| DLC ID | PLGG00BXA47N |
| California Status | California T24 Compliant |
| California Prop 65 | Lead |

| Additional | |
|------------|--|
| | |
| | |

Warranty

5 Year Limited











