




4" GEO / GROUND GRID (Load Class A-C) Gravel fill



Geo / Ground Grid (art.8710)



NOTES:

1. Please note, to be able to drive on this system, it must be filled with 3/4 inch gravel or larger.
2. 4" geo / ground grid system should be installed in accordance with the manufacturer's instructions and recommendations.
3. The manufacturer's technical consultation may be required to determine the correct load class.
4. The drawing of installation for the 4" geo / ground grid system is not an official guideline, but is a recommendation.
5. Layers shown in cross-section need to be compacted.
6. Geo-textile is to be used for stability and to prevent mixing between layers.
7. We recommend anchors on each corner of the grid, and throughout the perimeter. Needed on sloped installations, mostly.
8. Follow for updates to the instructions and recommendations on the website vodaland.ca

Application

driveways, parking, stone paver base, shed base, hot tub base, walkways, patios, erosion control up to 33 degrees

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS SURFACE FINISH TOLERANCES: LINEAR: ANGULAR:				FRESH		RETURN AND BREAK SHARP EDGES		DO NOT SCALE DRAWING	REVISION
DRAWN	NAME	SIGNATURE	DATE					VODALAND	
CHECKED								TITLE:	
APPROVED								4" geo / ground grid (Load Class A-C)	
APPROVED								ARTICLE:	
								8710	