



TL-342

CTL|THOMPSON, INC.
400 NORTH LINK LANE
FORT COLLINS, COLORADO 80524
(970) 206-9455

PRODUCT TESTING REPORTS
TITAN DECK FOOT ANCHORS
TIGA600 AND TIGA900

Prepared For:

intertek

Total Quality. Assured.

130 Derry Court
York, PA 17406

Attention: Mr. Kendall Leaman

Project Number: FC09763.000-470

Report Number: 1605 (Rev. 2)

October 29, 2021



October 29, 2021

Subject: Product Testing Report
Titan Deck Foot Anchors
TIGA600 and TIGA900

Project Number: FC09763.000-470
Report Number: 1605 (Rev. 2)

CTL|Thompson, Inc. has performed product testing on the products listed below in accordance with the supplied evaluation plan provided by Intertek (Report No: 104057475-YRK-01, dated: 04.23.2020). This report presents the product descriptions, test methods, test data and test summaries of the testing program.


Anchor types for each test were specified by Intertek. Installation instructions were provided by Titan Building Products and are attached in Appendix A. Per client request, testing excluded the load plate (HDKP) as shown in the installation instructions and shop drawings. Testing was only performed fully installed anchors.

Products included in this testing program are as follows:

Manufacturer ID	Shaft Size	Shaft Length	Auger Configuration
TIGA600	19 mm (0.748 in)	600 mm (23.62 in)	60 mm (2.362 in) / 83 mm (3.268 in)
TIGA900		900 mm (35.43 in)	

This report provides the following testing results based on the following test methods:

Main Standard	Reference Standard / Section	Test
AC358	Section 3.11.3, 4.2.2	Torsion
AC336	ASTM D1143 Section 10.1.3	Compression Load Bearing
IBC	ASTM D3689 Section 8.1.2	Tension Load Test



Summary of Testing Results

Standard / Section	Test	Result Summary
AC358 / 4.2.2	Torsion	RTC ¹ = 128.3 ft-lbs
AC336 / 4.3.2 ASTM D1143 / 10.1.3	Compression Load Bearing	Clay (TIGA900) RLC ² = 1,391 lbs Clay (TIGA600) RLC = 1,146 lbs Sand RLC = 6,285 lbs
ASTM D3689 / 8.1.2	Tension Load Test TIGA600	Clay RMLC ³ = 638 lbs Sand RMLC = 3,762 lbs
ASTM D3689 / 8.1.2	Tension Load Test TIGA900	Clay RMLC ³ = 1,244 lbs Sand RMLC = 4,001 lbs

¹ RTC = Reported Torque Capacity

² RLC = Reported Load Capacity (at 0.5" Deflection)

³ RMLC = Reported Maximum Load Capacity

We appreciate the opportunity to work with you on this project. If you have any questions regarding the information provided in this report, please do not hesitate to contact us.

Sincerely,
CTL|THOMPSON, INC.

Ryan S. Beck, P.E.
Associate Engineer
Accredited Laboratory Manager

Reviewed by:

R.B. "Chip" Leadbetter, III, P.E.
Senior Geotechnical Engineer
Accredited Laboratory Director

Report Authorized for Release:

Revision Log

Date	Revision No.	Explanation	By
09.24.2021	0	Initial Issue	R. Beck, Manager
09.27.2021	1	Include Extra Testing on TIGA600	R. Beck, Manager
10.29.2021	2	Additional Tension Testing on TIGA900	R. Beck, Manager



TABLE OF CONTENTS

Section 1: Titan Deck Foot Anchors (TIGA600 and TIGA900)

- A. Torsion
- B. Compression Load Bearing
- C. Tension Load Test

Section 2: Test Site Geotechnical Reports

Loveland #5: West 50th Street and Wilson Avenue, Loveland, CO
Platteville #1: 17988 CR32, Platteville, CO

Section 3: IAS Accreditation Certificate

Appendix A: Installation Instructions

Appendix B: Supplied Documentation

Appendix C: Equipment Calibration Records

SECTION 1:

TITAN DECK FOOT ANCHORS TIGA600 AND TIGA900



TORSION



Client:	Intertek
Job Number:	FC09763.000
Product:	TIGA900

Reference Method

Tests were conducted according to ICC-ES AC358 (4.2.2.1.3), and CTL|Thompson's test procedure TP 1.3.1.

Standard Procedure

Shaft dimensions, shaft length, auger diameters, auger thickness, and pitch were recorded for all specimens. A torsion fixture was used to accommodate the augers. Each specimen was loaded and tested in the torque machine (see Figure 1). Applied torque and angle deformation were recorded. Maximum torsion resistance was taken as that required to achieve 0.5 shaft revolution per foot of shaft length or that which causes failure of the shaft, whichever occurred first.






Figure 1. Torsion Test Setup

Deviations from Standard Procedure

There were no significant deviations from the standard procedure.

	ICC TESTING GROUP REPORT CTL Thompson, Inc. – Fort Collins	Issue Date:	Rev:	
		10.29.2021	2	
Title:		Report No.	Page #:	
TP 1.3.1 Torsion Capacity Test Report		1605A	2 of 5	

Summary of Results

Specimen Number	Auger Configuration	Shaft Diameter	Shaft Length	Maximum Torsion Resistance (ft-lbs) ¹	Deviation from Mean (%)	Reported Torque Capacity (ft-lbs)	Failure Mode ²
L1	60 mm (2.362 in) / 83 mm (3.268 in)	19 mm (0.748 in)	900 mm (35.43 in)	124.6	-2.86%	128.3	Shaft Torsion
L2				128.5	+0.18%		Shaft Torsion
L3				131.7	+2.68%		Shaft Torsion

¹ Per AC358 Section 4.2.2.2.3

² Based on the exposed length of the specimen and the provided failure criteria of 0.5 a revolution per foot shaft length, the required rotation for failure was equal to 472.5 degrees.

COMPRESSION LOAD BEARING



Client:	Intertek
Job Number:	FC09763.000
Product:	TIGA900 and TIGA600 (Clay)

Reference Method

Tests were conducted according to ICC-ES AC336 (4.3.2), and ASTM D1143 (10.1.3) Maintained Load Test Method.

Standard Procedure

The anchors were installed per instructions provided by the manufacturer. The final installation torque was recorded after installation. Load and deflection were recorded at intervals of about 25% up to the design load capacity. Tests were stopped when the measured load when the net deflection exceeded 0.5 inches.






Figure 1. Compression Load Test Setup

Deviations from Standard Procedure

There were no significant deviations from the standard procedure.

	ICC TESTING GROUP REPORT CTL Thompson, Inc. – Fort Collins		Issue Date: 10.29.2021	Rev: 2	
	Title: TP 2.2.1 Compression Load Bearing Test Report		Report No. 1605B	Page #: 2 of 20	

Summary of Results

Test Site	Specimen	Measured Installation Torque (ft-lbs)	Measured Load Capacity at 0.5" Deflection (lbs) ¹	Deviation from Mean (%)	Reported Load Capacity (lbs) ²
Loveland #5 (Clay)	LC1	37.2	1,510	-6.33%	1,391
	LC2	31.9	1,391	-13.67%	
	LC3	44.2	1,934	+20.01%	
	LC4	26.8	1,122	-2.09%	1,146
	LC5	24.3	1,170	+2.16%	
	LC6	25.7	1,145	-0.07%	
Platteville #1 (Sand)	PC1	97.9	6,314	+0.46%	6,285
	PC2	98.3	7,175	+14.17%	
	PC3	90.1	5,365	-14.63%	

¹ Per AC336 Section 3.5, the settlement at the design load shall be no greater than 0.5-inches.

² Per AC336 Section 4.3.1 and Intertek Evaluation Plan Section 5.6.2, should any individual result deviate more than 15% from the average, the lowest of the three tests shall apply.

Compression Load Bearing Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.14.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC1
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	37.2
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.14.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

1,612
1,510

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



ACCREDITED
Testing Laboratory

Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.14.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC2
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	31.9
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.14.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

1,561
1,391

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

Compression Load Bearing Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC3
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	44.2
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.14.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

2,428
1,934

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Brandon Edwards

Specimen Number: LC3



Measurements

Load (lbs)	Net Def (in)
78	0.000
366	0.009
360	0.010
353	0.011
349	0.011
626	0.061
615	0.062
604	0.063
588	0.065
846	0.100
804	0.102
804	0.104
792	0.105
1,090	0.159
1,074	0.163
1,061	0.165
1,043	0.171
1,372	0.254
1,345	0.259
1,321	0.263
1,303	0.266
1,658	0.368
1,620	0.374
1,603	0.379
1,583	0.384

Load (lbs)	Net Def (in)
1,902	0.450
1,862	0.455
1,836	0.460
1,814	0.467
2,160	0.561
2,127	0.571
2,098	0.579
2,080	0.585
2,428	0.770
2,373	0.782
2,342	0.790
2,324	0.799
1,632	0.803
1,636	0.803
1,272	0.800
1,276	0.800
635	0.790
644	0.789
0	0.767
0	0.764

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.09.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC4
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	26.8
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.09.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

1,359

Capacity at 0.5 inch Deflection (lbs):

1,122

Per AC336, Section 3.5

Compression Load Bearing Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.09.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC5
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	24.3
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.09.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):
Capacity at 0.5 inch Deflection (lbs):

1,234
1,170

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.09.2021
Technician:	Brandon Edwards



Specimen Number: LC5

Measurements

Load (lbs)	Net Def (in)
20	0.000
218	0.016
213	0.016
209	0.017
215	0.017
444	0.058
448	0.059
451	0.061
437	0.062
693	0.112
675	0.115
679	0.118
666	0.122
915	0.237
921	0.238
932	0.239
895	0.242
1,085	0.380
1,083	0.385
1,092	0.389
1,092	0.395
1,234	0.586
1,221	0.610
1,210	0.636
1,199	0.676

Load (lbs)	Net Def (in)
915	0.668
937	0.668
686	0.658
677	0.656
344	0.639
337	0.634
0	0.604
0	0.596

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



ACCREDITED
Testing Laboratory

Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.10.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	LC6
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	25.7
SPT Blowcount at Depth:	11/12
Nearest Test Reaction (ft):	5
Installation Date:	09.09.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

1,165
1,145

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



ACCREDITED
Testing Laboratory

Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.16.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	PC1
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	97.9
SPT Blowcount at Depth:	13/12
Nearest Test Reaction (ft):	5
Installation Date:	09.15.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):

6,464
6,314

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.16.2021
Technician:	Brandon Edwards

Specimen Number: PC1



Measurements

Load (lbs)	Net Def (in)
67	0.000
289	0.002
284	0.002
282	0.002
277	0.002
548	0.004
542	0.004
535	0.004
531	0.004
812	0.006
801	0.008
792	0.008
786	0.008
1,094	0.021
1,077	0.022
1,066	0.022
1,057	0.022
1,356	0.038
1,336	0.038
1,319	0.039
1,301	0.040
1,654	0.061
1,636	0.062
1,616	0.064
1,596	0.065

Load (lbs)	Net Def (in)
1,905	0.081
1,891	0.083
1,880	0.083
1,871	0.085
2,160	0.101
2,151	0.102
2,135	0.104
2,109	0.104
2,431	0.123
2,404	0.124
2,373	0.125
2,349	0.127
2,719	0.142
2,690	0.145
2,675	0.146
2,657	0.150
3,008	0.163
2,990	0.164
2,972	0.166
2,957	0.167
3,230	0.177
3,219	0.178
3,203	0.180
3,199	0.182
3,501	0.194

Load (lbs)	Net Def (in)
3,487	0.197
3,478	0.199
3,461	0.200
3,763	0.212
3,749	0.214
3,738	0.216
3,723	0.219
4,044	0.233
4,031	0.235
4,018	0.237
4,000	0.240
4,306	0.261
4,289	0.263
4,271	0.266
4,260	0.272
4,564	0.284
4,548	0.292
4,511	0.293
4,491	0.297
4,850	0.312
4,833	0.315
4,815	0.320
4,790	0.324
5,106	0.345
5,081	0.347

Load (lbs)	Net Def (in)
5,061	0.350
5,030	0.354
5,376	0.371
5,345	0.376
5,323	0.378
5,301	0.383
5,649	0.399
5,621	0.406
5,601	0.409
5,565	0.414
6,020	0.462
6,018	0.463
6,029	0.466
6,002	0.470
6,449	0.513
6,435	0.518
6,464	0.519
6,442	0.522
4,910	0.523
4,943	0.523
3,862	0.504
3,916	0.502
2,602	0.481
2,630	0.477
1,405	0.459

Note:

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



ACCREDITED
Testing Laboratory

Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.21.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	PC2
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	98.3
SPT Blowcount at Depth:	13/12
Nearest Test Reaction (ft):	5
Installation Date:	09.21.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):
Capacity at 0.5 inch Deflection (lbs):

7,201
7,175

Per AC336, Section 3.5

Compression Load Bearing Test



CTL | THOMPSON
INCORPORATED



ACCREDITED
Testing Laboratory

Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.21.2021
Technician:	Brandon Edwards

Test Method

AC336 4.3
ASTM D1143

Specimen Specification


Specimen Number:	PC3
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	90.1
SPT Blowcount at Depth:	13/12
Nearest Test Reaction (ft):	5
Installation Date:	09.21.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Recorded Test Capacity (lbs):


5,672
5,365

Capacity at 0.5 inch Deflection (lbs):

Per AC336, Section 3.5

TENSION LOAD TEST



	<p align="center">ICC TESTING GROUP REPORT CTL Thompson, Inc. – Fort Collins</p>	Issue Date:	Rev:	
		10.29.2021	2	
Title:		Report No.	Page #:	
TP 2.3.1 Full Scale Tension Load Test Report		1605C	1 of 26	

Client:	Intertek
Job Number:	FC09763.000
Product:	TIGA600 and TIGA900

Reference Method

Tests were conducted according to ASTM D3689 (8.1.2) Quick Load Test Method.

Standard Procedure



The anchors were installed per instructions provided by the manufacturer. The final installation torque was recorded after installation. Load and deflection were recorded at intervals of approximately 5-15% of the estimated ultimate load capacity. Tests were stopped when plunging occurred and the pile could not maintain the test load, the maximum test load was recorded.



Figure 1. Tension Test Setup

Deviations from Standard Procedure

There were no significant deviations from the standard procedure.

	ICC TESTING GROUP REPORT CTL Thompson, Inc. – Fort Collins	Issue Date:	Rev:	
		10.29.2021	2	
Title:		Report No.	Page #:	
TP 2.3.1 Full Scale Tension Load Test Report		1605C	2 of 26	

Summary of Results – TIGA600

Test Site	Specimen	Measured Installation Torque (ft-lbs)	Measured Maximum Load Capacity (lbs)	Deviation from Mean (%)	Reported Average Maximum Capacity (lbs) ¹
Loveland #5 (Clay)	LT1	26.2	662	+3.72%	638
	LT2	28.7	685	+7.34%	
	LT3	20.1	567	-11.06%	
Platteville #1 (Sand)	PT1	98.2	3,707	-1.47%	3,762
	PT2	101.3	3,893	+3.49%	
	PT3	99.9	3,686	-2.03%	

¹ Per Intertek Evaluation Plan Section 5.6.2, should any individual result deviate more than 15% from the average, the lowest of the three tests shall apply.

Summary of Results – TIGA900

Test Site	Specimen	Measured Installation Torque (ft-lbs)	Measured Maximum Load Capacity (lbs)	Deviation from Mean (%)	Reported Average Maximum Capacity (lbs) ¹
Loveland #5 (Clay)	LT4	51.9	1,347	+8.25%	1,244
	LT5	44.3	1,080	-13.20%	
	LT6	50.8	1,306	+4.95%	
Platteville #1 (Sand)	PT4	93.1	3,886	-2.87%	4,001
	PT5	98.2	4,149	+3.70%	
	PT6	95.5	3,968	-0.84%	

¹ Per Intertek Evaluation Plan Section 5.6.2, should any individual result deviate more than 15% from the average, the lowest of the three tests shall apply.

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.10.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT1
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	26.2
SPT Blowcount at Depth:	11/12
Installation Date:	09.10.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	662
Maximum Net Deflection (in):	1.074

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.10.2021
Technician:	Ryan Beck

Specimen Number:	LT1
------------------	-----



Measurements

Load (lbs)	Net Def (in)
20	0.000
126	0.011
113	0.013
110	0.013
114	0.014
238	0.032
230	0.032
227	0.033
232	0.033
342	0.050
325	0.052
323	0.052
316	0.053
425	0.150
420	0.156
427	0.163
410	0.176
497	0.330
512	0.343
500	0.356
493	0.367
662	1.001
627	1.035
613	1.053
598	1.073

Load (lbs)	Net Def (in)
397	1.074
401	1.074
214	1.073
224	1.071
109	1.069
109	1.069
0	1.068
0	1.068

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Tension Load Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.10.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT2
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	28.7
SPT Blowcount at Depth:	11/12
Installation Date:	09.10.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	685
Maximum Net Deflection (in):	1.083

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.10.2021
Technician:	Ryan Beck



Specimen Number: LT2

Measurements

Load (lbs)	Net Def (in)
22	0.000
51	0.001
44	0.001
45	0.001
41	0.001
123	0.023
109	0.025
123	0.027
109	0.029
224	0.099
209	0.104
207	0.105
212	0.106
313	0.198
317	0.199
315	0.199
306	0.200
408	0.310
410	0.315
412	0.318
407	0.321
469	0.447
466	0.457
463	0.463
470	0.468

Load (lbs)	Net Def (in)
567	0.639
568	0.649
562	0.658
545	0.667
685	1.022
641	1.045
627	1.064
598	1.083
469	1.080
483	1.080
253	1.076
267	1.075
109	1.041
123	1.040
0	0.994
0	0.990

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.14.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT3
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	20.1
SPT Blowcount at Depth:	11/12
Installation Date:	09.14.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	567
Maximum Net Deflection (in):	1.051

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.14.2021
Technician:	Ryan Beck



Specimen Number: LT3

Measurements

Load (lbs)	Net Def (in)
12	0.000
85	0.024
80	0.025
81	0.025
75	0.026
160	0.060
156	0.060
152	0.060
151	0.060
213	0.115
211	0.122
206	0.132
203	0.132
258	0.220
247	0.220
256	0.225
254	0.226
322	0.310
312	0.318
316	0.325
313	0.326
405	0.415
407	0.418
406	0.421
400	0.425

Load (lbs)	Net Def (in)
470	0.546
453	0.547
447	0.547
443	0.548
567	0.981
563	1.004
546	1.024
532	1.051
377	1.043
371	1.043
246	1.028
256	1.028
113	0.999
116	0.999
0	0.980
0	0.976

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT1
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	108.2
SPT Blowcount at Depth:	13/12
Installation Date:	09.15.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	3,707
Maximum Net Deflection (in):	0.794

Tension Load Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Ryan Beck

Specimen Number: PT1



Measurements

Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)
21	0.000	2,872	0.305				
467	0.002	2,834	0.306				
435	0.002	2,843	0.306				
444	0.002	2,831	0.309				
429	0.002	3,241	0.390				
825	0.015	3,252	0.393				
806	0.016	3,214	0.394				
814	0.016	3,236	0.401				
826	0.016	3,653	0.514				
1,288	0.034	3,657	0.514				
1,244	0.035	3,617	0.514				
1,278	0.034	3,636	0.516				
1,243	0.035	3,707	0.726				
1,668	0.074	3,699	0.740				
1,647	0.075	3,667	0.764				
1,659	0.075	3,653	0.794				
1,618	0.075	3,042	0.784				
2,082	0.143	3,047	0.784				
2,052	0.143	1,976	0.783				
2,057	0.144	1,992	0.782				
2,037	0.144	908	0.774				
2,468	0.214	932	0.771				
2,419	0.214	0	0.691				
2,438	0.219	0	0.684				
2,441	0.220						

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT2
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	111.3
SPT Blowcount at Depth:	13/12
Installation Date:	09.15.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	3,893
Maximum Net Deflection (in):	0.757

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	09.15.2021
Technician:	Ryan Beck

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT3
Specimen I.D.:	TIGA600
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	23.62

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	2
Final Install Torque (ft-lbs):	109.9
SPT Blowcount at Depth:	13/12
Installation Date:	09.15.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	3,686
Maximum Net Deflection (in):	0.760

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.27.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT4
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	51.9
SPT Blowcount at Depth:	11/12
Installation Date:	10.27.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	1,347
Maximum Net Deflection (in):	0.875

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.28.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT5
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	44.3
SPT Blowcount at Depth:	11/12
Installation Date:	10.28.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	1,080
Maximum Net Deflection (in):	0.646

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.28.2021
Technician:	Brandon Edwards



Specimen Number: LT5

Measurements

Load (lbs)	Net Def (in)
13	0.000
117	0.000
112	0.000
109	0.001
106	0.001
224	0.002
215	0.002
206	0.003
201	0.003
331	0.011
315	0.012
306	0.012
299	0.012
435	0.043
416	0.045
404	0.045
395	0.046
538	0.107
530	0.109
531	0.110
533	0.110
652	0.165
650	0.166
649	0.167
644	0.167

Load (lbs)	Net Def (in)
756	0.239
754	0.240
743	0.241
750	0.242
865	0.330
862	0.332
852	0.333
861	0.334
977	0.399
974	0.400
972	0.401
968	0.403
1,080	0.576
1,015	0.603
977	0.626
941	0.646
745	0.646
756	0.645
495	0.633
509	0.632
253	0.631
275	0.631
0	0.591
0	0.586

Load (lbs)	Net Def (in)

Load (lbs)	Net Def (in)

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.28.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	LT6
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Loveland #5
Test Boring Hole:	TH-3
Soil Type:	Stiff Clay
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	50.8
SPT Blowcount at Depth:	11/12
Installation Date:	10.28.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	1,306
Maximum Net Deflection (in):	0.611

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.28.2021
Technician:	Brandon Edwards



Specimen Number:	LT6
-------------------------	-----

Measurements

Load (lbs)	Net Def (in)
14	0.000
114	0.011
106	0.011
101	0.011
98	0.011
222	0.021
209	0.021
212	0.021
216	0.021
331	0.030
329	0.030
321	0.030
324	0.030
448	0.051
444	0.052
437	0.052
445	0.053
550	0.071
544	0.071
544	0.072
539	0.072
660	0.106
657	0.107
648	0.108
654	0.108

Load (lbs)	Net Def (in)
765	0.148
755	0.149
758	0.149
747	0.150
868	0.200
863	0.201
857	0.202
846	0.203
977	0.251
967	0.252
964	0.253
965	0.254
1,088	0.310
1,084	0.311
1,076	0.311
1,079	0.313
1,184	0.366
1,177	0.374
1,173	0.384
1,158	0.400
1,306	0.516
1,289	0.539
1,280	0.579
1,285	0.610
730	0.611

Load (lbs)	Net Def (in)
748	0.611
480	0.605
501	0.604
247	0.590
272	0.587
0	0.559
0	0.553

Load (lbs)	Net Def (in)

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.26.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT4
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	93.1
SPT Blowcount at Depth:	13/12
Installation Date:	10.26.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	3,886
Maximum Net Deflection (in):	0.612

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.26.2021
Technician:	Brandon Edwards



Specimen Number:	PT4
-------------------------	-----

Measurements

Load (lbs)	Net Def (in)
33	0.000
214	0.000
209	0.000
206	0.000
204	0.000
428	0.001
422	0.001
415	0.001
408	0.001
627	0.005
615	0.005
603	0.005
596	0.005
839	0.015
822	0.015
808	0.015
800	0.015
1,049	0.029
1,031	0.029
1,023	0.029
1,011	0.029
1,245	0.044
1,223	0.044
1,206	0.044
1,193	0.044

Load (lbs)	Net Def (in)
1,449	0.063
1,426	0.064
1,405	0.064
1,392	0.065
1,654	0.096
1,621	0.097
1,600	0.097
1,584	0.098
1,867	0.139
1,843	0.139
1,818	0.140
1,794	0.140
2,079	0.165
2,047	0.166
2,020	0.167
1,994	0.167
2,272	0.184
2,238	0.186
2,215	0.186
2,192	0.187
2,480	0.220
2,436	0.221
2,399	0.221
2,385	0.222
2,682	0.251

Load (lbs)	Net Def (in)
2,638	0.252
2,600	0.253
2,582	0.253
2,887	0.283
2,835	0.284
2,794	0.285
2,762	0.286
3,094	0.321
3,041	0.322
3,007	0.323
2,973	0.323
3,366	0.397
3,332	0.407
3,314	0.414
3,309	0.422
3,886	0.524
3,836	0.550
3,768	0.579
3,756	0.611
3,079	0.612
3,087	0.609
2,028	0.602
2,043	0.599
1,137	0.589
1,150	0.584

Load (lbs)	Net Def (in)
488	0.551
504	0.550
1	0.513
1	0.510

Note:

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.26.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT5
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	98.2
SPT Blowcount at Depth:	13/12
Installation Date:	10.26.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	4,149
Maximum Net Deflection (in):	0.841

Tension Load Test



CTL | THOMPSON
INCORPORATED



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.26.2021
Technician:	Brandon Edwards

Test Method

ASTM D3689

Specimen Specification


Specimen Number:	PT6
Specimen I.D.:	TIGA900
Auger Size 1 (in):	2.362
Auger Size 2 (in):	3.268
Auger Thickness (in):	0.118
Shaft Dimensions (in):	0.748
Shaft Thickness (in):	0.118
Shaft Length (in):	35.43

Installation Information

Test Site Location:	Platteville #1
Test Boring Hole:	TH-1
Soil Type:	Silty Sand
Final Install Depth (ft):	3
Final Install Torque (ft-lbs):	95.5
SPT Blowcount at Depth:	13/12
Installation Date:	10.26.2021

Note: Installed Per Titan Building Products Installation Criteria

Results



Maximum Test Capacity (lbs):	3,968
Maximum Net Deflection (in):	0.832

Tension Load Test



Client:	Intertek
Job Number :	FC09763.000
Date Tested :	10.26.2021
Technician:	Brandon Edwards

Specimen Number: PT6



Measurements

Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)	Load (lbs)	Net Def (in)
37	0.000	1,461	0.072	2,707	0.186	3,945	0.806
219	0.008	1,425	0.072	2,691	0.191	3,889	0.832
211	0.008	1,409	0.073	2,695	0.200	2,997	0.831
207	0.008	1,393	0.073	2,916	0.226	3,012	0.830
201	0.008	1,667	0.083	2,912	0.229	2,073	0.832
426	0.026	1,660	0.083	2,900	0.236	2,094	0.832
413	0.026	1,628	0.083	2,888	0.247	1,067	0.824
405	0.026	1,650	0.084	3,123	0.287	1,093	0.824
398	0.026	1,869	0.096	3,111	0.292	510	0.800
646	0.035	1,820	0.097	3,122	0.298	539	0.793
630	0.035	1,801	0.097	3,108	0.306	0	0.688
617	0.035	1,784	0.098	3,315	0.353	0	0.688
610	0.035	2,089	0.117	3,309	0.361		
855	0.044	2,046	0.118	3,288	0.370		
851	0.044	2,012	0.118	3,299	0.383		
846	0.044	1,991	0.118	3,532	0.458		
845	0.044	2,286	0.136	3,529	0.466		
1,071	0.051	2,224	0.137	3,500	0.476		
1,068	0.051	2,200	0.137	3,482	0.489		
1,063	0.052	2,181	0.137	3,734	0.589		
1,050	0.052	2,499	0.158	3,742	0.597		
1,267	0.063	2,491	0.158	3,717	0.611		
1,264	0.063	2,485	0.158	3,701	0.625		
1,265	0.063	2,473	0.159	3,968	0.749		
1,212	0.063	2,712	0.179	3,939	0.775		

Note:

SECTION 2:

**TEST SITE
GEOTECHNICAL REPORTS**



September 4, 2020

Attention: Mr. Chip Leadbetter
Director of IAS Testing, Lab #342

Subject: ICC Evaluation Testing
Helical Pier Testing Site Loveland #5
West 50th Street and Florence Drive
Loveland, Colorado

CTL|Thompson, Inc., specifically the Fort Collins Geotechnical Engineering Group, performed a geotechnical investigation at Florence Drive and West 50th Avenue in Loveland, Colorado (Figure 1). Our helical pier testing lab is performing full-scale load tests at this site and is referring to this site as Loveland #5. Our scope of work included drilling five exploratory borings at the site, logging subsurface conditions encountered in the borings, collecting soil and bedrock samples at 5-foot intervals, conducting a laboratory testing program, and providing our opinions and recommendations for soil and bedrock properties for this site. This letter summarizes the results of our investigation.

Site Description

The site is located south of southwest of the intersection of 50th Street and Wilson Avenue in Loveland, Colorado (Figure 1). A residential development is under construction to the south of the site, and further development is planned in the area. Part of the proposed construction includes extending Florence Drive north and 50th Street west until they intersect. The borings are located southeast of this proposed intersection. At the time of our investigation, the site was agricultural land and had recently been plowed. Boring TH-2 was located on a fill pile.

Geology

The site is located in the Colorado Piedmont Section of the Great Plains Physiographic Province. The Colorado Piedmont is an elongated trough where overlying sediments were eroded adjacent to the east flank of the Rocky Mountains during mountain building events. Structurally, the site lies along the western edge of the Denver Basin, an accumulation of primarily Mesozoic sediments which underlie overburden soils at the site and are sources of fossil fuels in the region. The Dakota Hogback, a north-south trending ridge of sandstone that dips approximately 12 to 15 degrees to the east in this area, is located approximately 1¼ miles west of the site.

Surface soils at the site are mapped as Quaternary Slocum alluvium, water-deposited soils (USGS Map I-855-G, Colton, 1978). The Slocum alluvium is described as cobble and boulder gravel. Based on our borings drilled for this site and our experience in the area, we consider the surficial soils at the site to be pediment soils consisting of clay with sand and occasional small gravel mostly confined to thin layers or small buried rills or channels. The thickness of the pediment soils at the site was approximately 8 to 12 feet in our borings. Typically, the thickness of the pediment soils



decreases to the west, and is not present at the hogback. The Natural Resource Conservation Service (NRCS) has mapped the site as the Fort Collins loam. The Fort Collins loam is described as loam, a varying mixture of sand, silt and clay. The NRCS describes a few small areas of the Fort Collins loam as having a gravelly layer below a depth of 40 inches. NRCS soil data is limited to a depth of about 5 feet. The description of the Fort Collins loam appears to be consistent with the soils encountered our borings.

The near-surface bedrock that underlies the pediment soils in this area is the lower shale member of the Cretaceous Pierre Shale. The lower shale member is described as dark olive-gray bentonitic shale. The lower shale member in the area consists of claystone and shale. The Pierre Shale in this area typically dips 12 to 15 degrees to the east. However, variations in dip direction and slope are anticipated at the site. The thickness of the Pierre Shale at the site is believed to range from about 1,000 to 2,000 feet. No outcrops of the Pierre Shale were observed at the site.

Subsurface Conditions

Subsurface conditions encountered in our borings consisted of nil to 16 feet of sandy clay fill over 7 to 14 feet of sandy clay, underlain by weathered and competent claystone bedrock to the depths explored. Groundwater was not encountered in the borings during drilling. Unconfined compression testing of one sample of the clay indicated a unconfined compressive strength of 11,700 psf. Five unconfined compression tests of the claystone bedrock resulted in unconfined compressive strengths of 11,700 to 14,600 psf for weathered samples and 11,600 to 20,300 psf for unweathered samples. Samples of the sandy clay selected for laboratory testing had fines contents (percent passing the No. 200 sieve) of 62 to 84 percent. Atterberg limit testing indicated liquid limits of 41 to 49, and plasticity indices of 20 to 31. One sample of the claystone bedrock selected for laboratory testing had a fines content (percent passing the No. 200 sieve) of 98 percent. Atterberg limit testing indicated a liquid limit of 45, and a plasticity index of 26. Laboratory test results from samples of the fill materials were within the ranges measured in the overburden sandy clay encountered elsewhere at the site and from previous investigations. Further descriptions of the subsurface conditions are presented on our boring logs (Figure 2) and in our laboratory test results (Table I).

Soil and Bedrock Properties

We used the measured soil properties from the samples collected from this site to estimate appropriate strength parameters. Based on the laboratory test results and our experience with similar subsurface conditions, we believe the following ranges of properties can be used for the clay and claystone bedrock underlying this site.

Material	Friction Angle, Φ (deg)	Cohesion, c (psf)	Total Unit Weight (pcf)
Sandy Clay Fill	0	1,000 – 2,000	120 - 130
Sandy Clay	0	3,000 – 5,000	120 - 130
Claystone Bedrock	0	6,000 – 10,000	130 - 140






If you have any questions regarding the information provided in this letter, please contact the undersigned.

Sincerely,
CTL|THOMPSON, INC.

Reviewed by:

Taylor Ray, EIT
Staff Geotechnical Engineer

Spencer A. Schram, PE
Project Manager




VICINITY MAP
LOVELAND, COLORADO
NOT TO SCALE

LEGEND:

- TH-1
●
 INDICATES APPROXIMATE LOCATION OF EXPLORATORY BORING

Locations of Exploratory Borings

FIGURE 1



LEGEND:

- FILL, CLAY, SANDY, MOIST, VERY STIFF, BROWN (CL)
- CLAY, SANDY, MOIST, MEDIUM STIFF TO VERY STIFF, BROWN (CL)
- WEATHERED CLAYSTONE BEDROCK, SANDY, MOIST, FIRM TO MEDIUM HARD, GRAY, BROWN
- CLAYSTONE BEDROCK, SANDY, MOIST, HARD, GRAY, BROWN
- DRIVE SAMPLE. THE SYMBOL 18/12 INDICATES 18 BLOWS OF A 140-POUND HAMMER FALLING 30 INCHES WERE REQUIRED TO DRIVE A 2.5-INCH O.D. SAMPLER 12 INCHES.

NOTES:

1. THE BORINGS WERE DRILLED ON JULY 29, 2020 USING 4-INCH DIAMETER CONTINUOUS-FLIGHT AUGERS AND A TRUCK-MOUNTED DRILL RIG.
2. THESE LOGS ARE SUBJECT TO THE EXPLANATIONS, LIMITATIONS AND CONCLUSIONS IN THIS REPORT.
3. NO GROUNDWATER WAS ENCOUNTERED DURING THIS INVESTIGATION.
4. WC - INDICATES MOISTURE CONTENT (%).
 DD - INDICATES DRY DENSITY (PCF).
 SW - INDICATES SWELL WHEN WETTED UNDER OVERBURDEN PRESSURE (%).
 -200 - INDICATES PASSING NO. 200 SIEVE (%).
 LL - INDICATES LIQUID LIMIT.
 PI - INDICATES PLASTICITY INDEX.
 UC - INDICATES UNCONFINED COMPRESSIVE STRENGTH (PSF).
 SS - INDICATES SOLUBLE SULFATE CONTENT (%).



TABLE I
SUMMARY OF LABORATORY TESTING

BORING	DEPTH (FEET)	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	ATTERBERG LIMITS		UNCONFINED COMPRESSIVE STRENGTH (PSF)	PASSING NO. 200 SIEVE (%)	DESCRIPTION
				LIQUID LIMIT	PLASTICITY INDEX			
TH-1	4	12.9	105	49	31		83	CLAY, SANDY (CL)
TH-1	19	13.8	122			20,300		CLAYSTONE, SANDY
TH-2	9	8.2	109	40	23		79	FILL, CLAY, SANDY (CL)
TH-2	19	19.0	103	41	20		62	CLAY, SANDY (CL)
TH-3	14	17.1	116			14,600		CLAYSTONE, WEATHERED
TH-3	19	14.9	120			14,000		CLAYSTONE, SANDY
TH-4	4	14.1	107			11,700		CLAY, SANDY (CL)
TH-4	14	16.9	116			11,700		CLAYSTONE, WEATHERED
TH-4	19	14.3	121	45	26		98	CLAYSTONE, SANDY
TH-5	4	12.9	108	44	27		84	CLAY, SANDY (CL)
TH-5	14	15.4	120			11,600		CLAYSTONE, SANDY

* NEGATIVE VALUE INDICATES COMPRESSION.

May 12, 2010

Attention: Mr. Chip Leadbetter
Director of IAS Testing, Lab #342

Subject: ICC Evaluation Testing
Helical Pier Testing Site – Platteville #1
Platteville, Colorado

CTL|Thompson, Inc., specifically the Fort Collins Geotechnical Engineering Group, performed a geotechnical investigation at 17998 County Road 32, Platteville, Colorado (Figure 1). Our helical pier testing Lab is performing full scale load tests at this site and is referring to this site as Platteville #1. Our scope of work included drilling one exploratory boring at the site, logging subsurface conditions encountered in our boring, collecting soil and bedrock samples at intervals of 5 feet, conducting a laboratory testing program, and providing our opinions and recommendations for soil and bedrock properties for this site. This letter summarizes the results of our investigation.

Site Description

The site is located east of the Spear Canal (Figure 1). The area is primarily unimproved with dirt access roads. Ground cover at the site consists of native grasses, weeds, brush, and cactus.

Geology

The site is located in the Colorado Piedmont Section of the Great Plains Physiographic Province. The Colorado Piedmont is an elongated trough where overlying sediments were eroded adjacent to the east flank of the Rocky Mountains during mountain building events. The South Platte River is located approximately 6 miles to the west and 8 miles, or more, to the northwest and north. Sediments from rivers and wind were deposited contemporaneous with the formation of the piedmont and afterwards. Structurally, the site lies in the Denver Basin, an accumulation of Mesozoic sediments which underlie the eolian soils at the site and are sources of fossil fuels in the region.

Surface soils at the site are mapped as Quaternary age eolian (wind-blown) soils (USGS Map I-855-G, Colton, 1978). The eolian soils are described as clay, silt and sand. Linear features of the eolian deposits appear to be arranged in a general northwesterly-to-southeasterly direction, which is consistent with the direction of the prevailing winds and a sediment source (South Platte River) from the northwest. The thickness of the eolian soils can range from 3 feet to 50 feet. The Natural Resource Conservation Service (NRCS) has mapped the site as the Valent sand and Vona sand. The Valent and Vona sands are described as fine-grained, eolian sand and loamy sand. NRCS soil data is limited to a depth of about 5 feet. The description of the Valent sand and Vona sand appears to be consistent with the soils encountered in the upper 10 to 20½ feet of our boring.



The near-surface bedrock that underlies the eolian soils in this area is interpolated from the map as the Cretaceous Laramie Formation. The Laramie Formation in the area consists of claystone, shale, sandstone and several beds of coal. The Laramie Formation typically dips to the southeast in this area. However, variations in dip direction and slope are anticipated at the site. The thickness of the Laramie Formation can range from about 700 to 800 feet. No outcrops of the Laramie Formation were observed at the site.

Subsurface Conditions

Subsurface conditions encountered in our boring at the site consisted of about 20 to 21 feet of silty sand over weathered and unweathered claystone bedrock (Figure 2). A sample of the clayey sand selected for laboratory testing was non-plastic and had 32 percent particles passing the No. 200 sieve (Figure 3). The results of laboratory tests are summarized in Table 1.



Soil and Bedrock Properties

We used the measured soil properties from the samples collected from this site to estimate appropriate strength parameters. Based on the laboratory test results and our experience with similar subsurface conditions, we believe the following ranges of properties can be used for the sand and claystone bedrock underlying this site.

Material	Friction Angle, Φ (deg)	Cohesion, c (psi)	Total Unit Weight (pcf)
Silty Sand	28 - 32	0	120 - 130
Weathered Claystone Bedrock	0	3,000 - 4,000	120 - 125
Claystone Bedrock	0	4,000 - 6,000	125 - 135



If you have any questions regarding the information provided in this letter, please contact the undersigned.

Sincerely,
CTL|THOMPSON, INC.

Thomas W. Finley, CPG
Senior Geologist



Reviewed by:

Eric D. Bernhardt, PE
Project Manager



APPROXIMATE
SCALE: 1" = 700'



VICINITY MAP
PLATTEVILLE, CO AREA
NOT TO SCALE


LEGEND:



INDICATES APPROXIMATE
LOCATION OF EXPLORATORY
BORING

Location of Exploratory Boring

TH-1



LEGEND:



SAND, SILTY, MOIST, MEDIUM DENSE, BROWN (SM)



WEATHERED CLAYSTONE, MOIST, MEDIUM HARD, BROWN, GRAY



CLAYSTONE BEDROCK, MOIST, HARD, BROWN, GRAY, RUST




DRIVE SAMPLE. THE SYMBOL 13/12 INDICATES 13 BLOWS OF A 140-POUND HAMMER FALLING 30 INCHES WERE REQUIRED TO DRIVE A 2.5-INCH O.D. SAMPLER 12 INCHES.

NOTES:

1. THE BORING WAS DRILLED ON OCTOBER 27, 2009 USING 4-INCH DIAMETER CONTINUOUS-FLIGHT AUGER AND A TRUCK-MOUNTED CME-55 DRILL RIG.
2. APPROXIMATE BORING LOCATION IS SHOWN ON FIGURE 1.
3. GROUND WATER WAS NOT ENCOUNTERED DURING THIS INVESTIGATION.
4. THIS LOG IS SUBJECT TO THE EXPLANATIONS, LIMITATIONS AND CONCLUSIONS IN THIS LETTER.

Summary Log of Exploratory Boring

FIGURE 2



CLAY (PLASTIC) TO SILT (NON-PLASTIC)	SANDS			GRAVEL			
	FINE	MEDIUM	COARSE	FINE	COARSE	COBBLES	
Sample of <u>SAND, SILTY (SM)</u>				GRAVEL	<u>0 %</u>	SAND	<u>68 %</u>
From <u>TH - 1 AT 4 FEET</u>				SILT & CLAY	<u>32 %</u>	LIQUID LIMIT	<u>NL</u>
				PLASTICITY INDEX			<u>NP</u>



TABLE I

SUMMARY OF LABORATORY TESTING

BORING	DEPTH (FEET)	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	ATTERBERG LIMITS		PASSING NO. 200 SIEVE (%)	DESCRIPTION
				LIQUID LIMIT	PLASTICITY INDEX		
TH-1	4	7.9		NL	NP	32.4	SAND, SILTY (SM)

SECTION 3:

**IAS ACCREDITATION
CERTIFICATE**





SCOPE OF ACCREDITATION

IAS Accreditation Number	TL-342
Company Name	CTL/Thompson, Inc.
Address	400 N. Link Lane Ft. Collins, CO 80524
Contact Name	Chip Leadbetter, Senior Engineer
Telephone	(970) 206-9455
Effective Date of Scope	April 8, 2019
Accreditation Standard	ISO/IEC 17025: 2005

CMT

- ASTM C31/C31M Standard practice for making and curing concrete test specimens in the field (field cure only)
- ASTM C39/C39M Standard test method for compressive strength of cylindrical concrete specimens (test on field cured specimen only)
- ASTM C231 Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method

Structural

- ASTM D1143/D1143M Standard test methods for deep foundations under static axial compressive load
- ASTM D3689/D3689M Standard test methods for deep foundations under static axial tensile load
- ASTM D3966/D3966M Standard test methods for deep foundations under lateral load
- ICC-ES AC237 Non-prestressed Deformed High Strength Steel Bars for concrete Reinforcement
- ICC-ES AC336 Acceptance Criteria for Bearing Pin Piers
- ICC-ES AC358 Helical pile systems and devices (test methods referenced in sections 4.1.1 (type A), 4.1.2 (type B), 4.2.1, 4.2.2, 4.2.3, 4.2.4, 4.3, 4.4.1 and 4.4.2)
- ICC-ES AC406 Belled segmented pipe foundation systems and devices (test methods referenced in sections 4.1.1 (side load), 4.2.2, 4.2.3 and 4.4.1))
- ICC-ES AC443 Screw foundation systems (SFSs) (test methods referenced in sections 3.0 and 4.0)

APPENDIX A:

INSTALLATION INSTRUCTIONS



INSTALLATION | DECK FOOT ANCHOR™

IMPORTANT NOTE :



CHECK YOUR LOCAL BUILDING DEPARTMENT FOR HEIGHT REQUIREMENTS REGARDING FREE STANDING STRUCTURES.

1 Remove Sod and any organic material. Add 2" – 3" of 1/2" Crushed Stone or Stone Dust Base

DECK FOOT ANCHOR™

TOOLS NEEDED:

- 350 FT.-LBS. ELECTRIC CORDED 1/2" IMPACT WRENCH
- 12 MM AND 24 MM, 6 POINT DEEP IMPACT SOCKET
- 12 POINT SOCKET

1/4 x 3" lag screws sold separately.

2

NUT
LOAD PLATE
AUGER
Assemble parts.

3

Drive Anchor down.

4

STOP when plate contacts ground and the nut contacts top of plate.

5

Use 24 mm socket and compress plate against top of washer.

6

Install bracket, washer and nut.
Make side-to-side fine adjustments before fastening.

7

Install screw at bottom of each hole. Stop as soon as screw contacts bracket.

HOUSE

FOOTING LAYOUT GUIDE

ASSUMES 1800 PSF SOIL

For 1500 psf soil, 5'-6" center to center max. spacing

Maximum Joist cantilever 24"

Maximum Beam cantilever 24"

WE RECOMMEND ADDING ONE MORE FOOTING TO INNER BEAMS.

Joists on beam

Hanging joists

As low as 2" above grade

Post / Beam / Joist Bracing

6'-0" max recommended

* Check local codes for height restrictions for free standing structures.

Optional Deck Frame Bracing

TITAN DECK FOOT ANCHOR™ / TIDP442 / TIDP662 / TIDKP / TIGA600 / TIGA900

PATENT NO US 9,309,688

ATTENTION: Before beginning work, consult with local building officials or engage professionals to ensure that this product is appropriate for your intended use or help clarify if these warnings are unclear or if you do not understand any of the information in this installation guide. Always comply with applicable building codes and be advised that building codes may vary.

ADVERTENCIA : Antes de comenzar a trabajar, consulte con funcionarios de la construcción local o contrate profesionales para asegurarse de que este producto sea apropiado para la aplicación deseada o para para ayudar a clarificar en caso de que estas advertencias no sean claras o en caso de que usted no comprenda parte de la información de esta guía de instalación. Siempre cumpla con los códigos de construcción aplicables y sepa que los códigos de la construcción pueden variar.

ATTENTION : Avant de commencer le travail, consultez les autorités locales en construction ou embauchez des professionnels pour assure que ce produit est approprié pour l'application que vous avez en vue ou pour aider à clarifier ces instructions si elles ne sont pas claires ou si vous ne comprenez pas quelque information que ce soit dans ce guide d'installation. Conformez vous toujours aux codes du bâtiment qui s'appliquent à sachez que les codes du bâtiment peuvent varier d'un endroit à un autre.

IN NO EVENT SHALL TITAN BUILDING PRODUCTS BE LIABLE FOR ANY LOSS OR DAMAGE, DIRECT OR OTHERWISE, WHICH RESULTS FROM THE IMPROPER INSTALLATION OR USE OF THIS PRODUCT. IF FOR ANY REASON TITAN BUILDING PRODUCTS BECOMES LIABLE FOR LOSS OR DAMAGE, DIRECT OR OTHERWISE, THE AGGREGATE LIABILITY OF TITAN BUILDING PRODUCTS SHALL BE LIMITED TO THE RETAIL PURCHASE PRICE OF THE PRODUCTS.



QUESTIONS? CONTACT US TOLL FREE
1-866-577-8868



titanbuildingproducts.com



INSTALLATION | DECK FOOT ANCHOR™



Introducing Terra-Shift™

“A SHOCK ABSORBER SYSTEM FOR YOUR DECK”



The Titan Deck Foot Anchor™ uses our patented Terra-Shift™ post bracket system to help keep soil around the anchor undisturbed and prevent damage to all post and beam and other structural connections.



Here is how it works:

The fastener slide holes reduce friction between the

post and bracket just enough so that if the soil shifts or expands unevenly along a series of footings under a beam, the post is free to slide vertically and then settle back to normal. It's like a shock absorbing system for your deck.



TITAN DECK FOOT ANCHOR™ / TIDP442 / TIDP662 / TIDKP / TIGA600 / TIGA900

PATENT Nº US 9,309,688

ATTENTION: Before beginning work, consult with local building officials or engage professionals to ensure that this product is appropriate for your intended use or help clarify if these warnings are unclear or if you do not understand any of the information in this installation guide. Always comply with applicable building codes and be advised that building codes may vary.

ADVERTENCIA : Antes de comenzar a trabajar, consulte con funcionarios de la construcción local o contrate profesionales para asegurarse de que este producto sea apropiado para la aplicación deseada o para para ayudar a clarificar en caso de que estas advertencias no sean claras o en caso de que usted no comprenda parte de la información de esta guía de instalación. Siempre cumpla con los códigos de construcción aplicables y sepa que los códigos de la construcción pueden variar.

ATTENTION : Avant de commencer le travail, consultez les autorités locales en construction ou embauchez des professionnels pour assure que ce produit est approprié pour l'application que vous avez en vue ou pour aider à clarifier ces instructions si elles ne sont pas claires ou si vous ne comprenez pas quelque information que ce soit dans ce guide d'installation. Conformez vous toujours aux codes du bâtiment qui s'appliquent à sachez que les codes du bâtiment peuvent varier d'un endroit à un autre.

QUESTIONS? CONTACT US AT 1-866-577-8868 IN NO EVENT SHALL TITAN BUILDING PRODUCTS BE LIABLE FOR ANY LOSS OR DAMAGE, DIRECT OR OTHERWISE, WHICH RESULTS FROM THE IMPROPER INSTALLATION OR USE OF THIS PRODUCT. IF FOR ANY REASON TITAN BUILDING PRODUCTS BECOMES LIABLE FOR LOSS OR DAMAGE, DIRECT OR OTHERWISE, THE AGGREGATE LIABILITY OF TITAN BUILDING PRODUCTS SHALL BE LIMITED TO THE RETAIL PURCHASE PRICE OF THE PRODUCTS.

QUESTIONS? CONTACT US TOLL FREE
1-866-577-8868



titanbuildingproducts.com

APPENDIX B:

**SUPPLIED
DOCUMENTATION**



TITAN DECK FOOT ANCHOR EVALUATION PLAN

PRODUCT EVALUATED
TITAN DECK FOOT ANCHOR

EVALUATION PROPERTY
2018 IRC - STRUCTURAL


REPORT NUMBER
104057475-YRK-01

ORIGINAL ISSUE DATE
04/23/20

LAST REVISED DATE
ORIGINAL

PAGES
16

DOCUMENT CONTROL NUMBER
SFT-BC-OP-19A
© 2017 INTERTEK



EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

TEST PLAN RENDERED TO:	
Company Name:	Titan Building Products
Address:	5450 Canotek Rd Unit 71 Ottawa, ON K1J 9G6 Canada
Contact Person:	Richard Bergman
Tel:	President
Email:	rbergman@Titanbuildingproducts.com

Table of Contents

1	Introduction	3
2	Product and Assembly Description	3
2.1.	PRODUCT AND/OR ASSEMBLY DESCRIPTION:.....	3
2.2.	MANUFACTURER'S INFORMATION	3
3	Reference Documents.....	3
4	Certification Requirements	4
5	Evaluation Method.....	4
6	Conclusion	9
7	APPENDIX	10
8	LAST PAGE & REVISION SUMMARY	16

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

1 Introduction

Intertek Testing Services NA Inc. (Intertek) is preparing this evaluation plan for Titan Building Products (TBP), on Titan Deck Foot Anchors. The evaluation plan will outline the requirements to obtain an Intertek Code Compliance Research Report (CCRR) in accordance with the 2018 International Residential Code (IRC).

2 Product and Assembly Description

2.1. PRODUCT DESCRIPTION:

The Titan Deck Foot Anchor is a fabricated steel surface footing plate with an integral auger anchor for use as footings supporting exterior residential decks. The Titan Deck Foot Anchor is comprised of three primary components:

1. A steel bearing plate (footing). One size; nominally 12"x12"
2. A post base anchor bracket fixed to the top side of the footing plate to accommodate either a 4x4 or 6x6 wood deck post.
3. An auger style anchor beneath the footing plate for anchorage into foundation soils. Two lengths; nominally 24" and 36"

The three components are mechanically connected (bolted) at the footing plate.
See Appendix for component drawings

2.2. MANUFACTURER'S INFORMATION

	Owner/Listee of Product and Listing	Manufacturing Plant (If Different from Applicant/Listee)
Company Name:	Titan Building Products	Mai Van Dang Co., Ltd
Address:	5450 Canotek Rd Unit 71 Ottawa, ON K1J 9G6 Canada	Hoa Xa Industrial Zone Nam Dinh City - Nam Dinh Province Viet Nam
Contact Person:	Richard Bergman	Ms. Tam
Alternate Contact:		
Tel:	613-224-9477	84-28.3671811
Fax:	613-224-9713	84-28.3861550
Email:	rbergman@Titanbuildingproducts.com	madavuexport@gmail.com

3 Reference Documents

As part of this evaluation, Intertek has directly or indirectly used the following referenced documents:

- 2018 Residential Building Code (IRC)
- ICC-ES Acceptance Criteria for Precast Concrete Pier Foundation Assemblies, AC336

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

- ICC-ES Acceptance Criteria for Helical Pile Systems and Devices, AC358
- ASTM D1143 Standard Test Method for Piles Under Static Axial Compressive Load
- ASTM D3689 Standard Test Method for Induvial Piles under Static Axial Tensile Load
- ICC-ES Acceptance Criteria for Joist Hangers and Similar Devices, AC13
- AISI S100-16, North American Standard for the Design of Cold-Formed Steel Structural Members
- National Design Specification for Wood Construction, NDS-2015

4 Certification Requirements

To obtain certification, the following steps will need to be conducted after this test plan has been reviewed and approved by all parties:

1. Applicant, and manufacturer, if different, will need to sign the Client Information Sheet (CIS), and Certification Agreement.
2. Specimens for testing must be sampled by Intertek at the manufacturing location, or otherwise shown to be of normal manufacture.
3. An Intertek representative will conduct an audit of the manufacturing process and quality control program (usually at the same time as the sampling visit) to develop a Factory Audit Manual (FAM). The FAM will be used during follow-up inspections after the product is Listed with Intertek to ensure that the product is made the same as during the qualification period.
4. The FAM will be developed in accordance with ICC-ES AC10 from documentation supplied by the manufacturer and from documentation collected during the audit. The Applicant, and manufacturer, if different, must sign the FAM.
5. Successful completion of engineering and/or testing outlined in this Evaluation Plan will qualify the product for an Intertek certification in compliance with the 2018 international Residential Code (IRC) after the below steps are completed. A complete set of installation instructions are required for any assembly configurations.
6. During the testing phase, you will be provided with Intertek's labeling procedure which will outline the minimum marking requirements. This will need to be drafted by you, and then approved by Intertek.
7. On completion of a successful test program, a Listing Report will be created and include all the test reports and/or evaluations, FAM, and approved Label.
8. An Initial Factory Assessment (IFA) must be conducted after the Listing is published, and before receiving the Authorization to Mark (ATM). The IFA ensures that all provisions of the FAM have been implemented at the manufacturing location.

5 Evaluation Method

5.1. Scope and General Overview: Evaluation scope includes evaluation of code requirements for materials used and structural performance of the footing system to establish design capacities. For use under the IRC, allowable compressive loads will be used to draw equivalence to conventional footing sizes for given soil bearing capacities specified in IRC Table 507.3.1 for residential decks. The scope of evaluation shall include:

- Configurations listed in Section 2.1
- Two loading directions:

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

- Load-bearing (compression)
- Uplift (Pull-out)
- Lateral loads are not included within the scope of this evaluation.
- Soil types TBD. TBP shall specify the soil types to include in the evaluation in accordance with the class of materials listed in IRC Table R401.4.1. For planning purposes, it is assumed at this time that two soil classes will be evaluated. Examples include:
 1. Non-expansive stiff clays (CL, CH)
 2. Silty Sand (SM, SP)

Where the conditions to be evaluated require in-situ load testing, the evaluation method shall be in accordance with ICC-ES AC336. For uplift (pull out) loading, test method ASTM D3689 shall be used in lieu of ASTM D1143 specified by AC336 for compressive loads. Use of ASTM D1143 and D3689 for compressive and uplift loads is consistent with IBC Chapter 18 foundation design. AC336 is chosen based on its limited scope (residential decks) and applicable foundation design principles (mini piles).

Where the conditions to be evaluated require the helix of the auger anchor to act as a structural component for load bearing, relative provisions of AC358 for helical piles are employed.

5.2. Sampling and Prequalification Audit

5.2.1. A prequalification audit (PQA) shall be conducted at the manufacturing plant to document and verify material specifications, manufacturing process and quality control procedures. Witnessing and/or selection of samples for testing can be conducted in conjunction with the PQA. Samples provided for testing prior to the PQA may be used only if there is product marking sufficient to facilitate traceability to production records and material certs for subsequent verification.

5.3. Materials

Detailed material specifications including steel grades and corrosion protection shall be provided for review and shall conform with minimum requirements of the code and code referenced standards.

5.4. Design Calculations

Where evaluation methods require engineering calculations, the calculations shall be in accordance with code referenced design standards and shall be signed and sealed by a licensed design professional.

5.5. Torsion Resistance

Installation torque capacity of the helix and shaft shall be evaluated in accordance with AC358 Section 3.12.4 and 4.2.2. Specified installation methods shall ensure that forces imposed during installation do not exceed design limits of the assembly either by limits of equipment used or torque measurement devices.

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

5.6. In-Situ Testing

- 5.6.1. A soils investigation and report by a licensed geotechnical engineer shall be provided in accordance with AC336 Section 4.3.1 for each site to establish classification of the soils used in testing and a value within 10% of the values for which recognition is sought.
- 5.6.2. A minimum of three tests shall be conducted for each installation configuration and loading condition. Should any individual result vary by more than 15% from the average, the lowest of the three shall apply or, the proponent may run two additional tests and use the average value from the total of five.
- 5.6.3. Compressive load tests shall be conducted in accordance with AC336 Section 4.3.2. For uplift loading, the quick load test procedure of D3689 shall be used.

5.7. Load Bearing (Compression) Capacity

- 5.7.1. Installation Condition 1 – Footing plate is placed on undisturbed load-bearing soil in accordance with building code requirements as follows:
 - a. R403.1.4 Minimum Depth. Not less than 12 inches below undisturbed ground surface
 - b. R403.1.4.1 Frost protection. Not required for decks not supported by a dwelling. However, when the Titan Deck Foot Anchor is anchored below frost line, frost heave forces could be imposed on the footing plate. See uplift capacity for resistance to frost heave.

Bearing capacity shall be evaluated by engineering calculations for strength and stiffness of the footing plate in accordance with AISI S100 to resist the maximum specified soil bearing capacity using conventional shallow foundation design methodology.

- 5.7.2. Installation Condition 2 - Footing plate is not placed on undisturbed load-bearing soil in accordance with building code requirements. Plate is located on loose surface soils or noncompacted fill.

Under these conditions, load bearing capacity would rely on the auger anchor acting like a pile. Evaluation shall be in accordance with IBC Section 1810.3.3.1.9 and applicable provisions of AC358 requiring engineering calculations for the auger assembly (helix and shaft) and testing in accordance with ASTM D1143 (See 5.4).

Note: The TBP Deck Anchor system is a relatively shallow installation compared to traditional helical piles addressed in building code under deep foundations. As such, correlations of load capacity with installation torque referenced in IBC Section 1810.3.3.1.9 and AC358 are not applicable. The TBP Deck Anchor system will be evaluated at a specified depth of installation as opposed to the required installation depth based on torque resistance and testing in accordance with AC336 is more appropriate.

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

5.8. Uplift (Pull Out) Capacity

The auger anchor is installed in undisturbed soil and is evaluated for resistance to uplift forces from wind or frost heave. TBP shall specify the minimum depth below undisturbed soil for this evaluation.

Evaluation shall be in accordance with applicable provisions of AC308 requiring engineering calculations for the auger anchor assembly (helix and shaft) and testing in accordance with ASTM D3689 (See 5.4)

5.9. Post Base Bracket

The metal post base bracket shall be evaluated for vertical compression and uplift loading in accordance with AC13 requiring testing and fastening calculations in accordance with the NDS.

5.9.1. Load testing for load-bearing compression and uplift (tension) shall be conducted in accordance with ASTM D7147. Testing is required for each wood species (or group) based on specific gravity (G) for the wood species in accordance with the NDS. For planning purposes, two specific gravity values are proposed for testing.

- 1) G=0.5 for DF and SYP
- 2) G=0.42 for HF and SPF

5.9.2. Test specimen materials. The following properties shall be determined for the materials used in test specimens:

- 3) Tensile strength of bracket steel
- 4) Specific gravity of wood post
- 5) Bending yield strength of fasteners

Where material properties of test specimens exceed the minimum specified values, load test results must be adjusted in accordance with Section 13.5.

5.9.3. Allowable load bearing capacity shall not exceed the load bearing capacity of the wood post determined in accordance with the NDS including end bearing and lateral resistance of the plate to wood post fasteners.

5.9.4. Allowable uplift capacity shall not exceed the lateral resistance of the plate to wood post fasteners determined in accordance with the NDS.

Optional: A commercially available metal post base of similar design (single anchor bolt in center of base) that has been evaluated in accordance with AC13 and recognized in a valid product evaluation report, may be specified for use in the Titan Foot Anchor system.

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

Tests for Helical System

Main Standard	Test	Referenced Standard	No. of Samples	Test Details/Comments	Test Laboratory
AC336	Compression Load Bearing	ASTM D1143	3 min. See 5.6.2	Required for each soil type (material classification)	Intertek-PSI
IBC	Tension (uplift/pull out)	ASTM D3689	3 min. See 5.6.2	Required for each soil type (material classification) Tested at minimum depth specified below undisturbed soil.	Intertek-PSI
AC358	Torsion	AC358, 3.11.3 and 4.2.2	3	Shaft and Helix Plate	TBD

Tests for Post Base Bracket – Tests specified are required for each bracket size (4x4, 6x6, etc.)

Main Standard	Test	Referenced Standard	No. of Samples	Test Details/Comments	Test Laboratory
AC13	Steel Tensile Strength	ASTM A370	5	Required for each steel material used to manufacture the test specimens. Traceability is required for each bracket tested.	TBD
AC13	Specific Gravity and Moisture Content	ASTM D2395 and ASTM D4442	3	Tests required for each wood member used in testing.	TBD
AC13	Bending Yield Strength of Fasteners	ASTM F1575	15	Tests required for each fastener from the same manufacturers lot.	TBD
AC13	Direct Load Capacity	ASTM D7147	3	Tests required for each size and wood species group (Specific Gravity) a) 4x4 w/G=0.42 b) 6x6w/G=0.42 c) 4x4 w/G=0.5 d) 6x6 w/G=0.5 Optionally, tests may be run for G=0.42 only and values can apply for wood with G=0.42 or greater.	TBD
AC13	Uplift Load Capacity	ASTM D7147	3		

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

6 Conclusion

Intertek has prepared this evaluation plan for Titan Building Products, on titan Deck Foot Anchor systems. The plan as described in this report outlines the requirements for a Code Compliance Research Report (CCRR) for the 2018 International Residential Code (IRC). Once the test plan is accepted, a separate project will need to be initiated for testing, evaluation and issuance of the certification and CCRR.

This test plan specifies the minimum number of tests contingent on variation tolerances in test results. Should variation exceed the specified tolerances, additional testing may be required.

INTERTEK TESTING SERVICES NA INC.

Reported by:



Craig H. Wagner, P.E.
Chief Engineer – Building & Construction

Reviewed by:



Michael Beaton, P.E.
Director, Special Projects



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01


Date: 04/23/20

7 APPENDIX - DRAWINGS

EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01


Date: 04/23/20



EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01


Date: 04/23/20



EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01


Date: 04/23/20



EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20



EVALUATION PLAN FOR TITAN DECK FOOT ANCHOR

Report No.: 104057475-YRK-01

Date: 04/23/20

8 LAST PAGE & REVISION SUMMARY

DATE	SUMMARY	REPORTER	REVIEWER
4/23/20	Original	C. Wagner	M. Beaton



NHÀ MÁY ĐÚC THÉP HỢP KIM CAO VICO

Số: 0001.PT/VC

Địa chỉ: Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 15 tháng 03 năm 2021.

KẾT QUẢ THỬ NGHIỆM TEST RESULT

AUGER TUBING

1. Tên mẫu/Sample: Tôn 1.6mm
2. Khách hàng/Customer: CÔNG TY MAI VĂN DẰNG
3. Kết quả/Results:

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
•	Carbon (C)		0.075
•	Silicon (Si)		0.0041
•	Manganese (Mn)		0.122
•	Phosphorus (P)		0.0100
•	Sulfur (S)		0.0038
•	Chromium (Cr)		0.042
•	Molybdenum (Mo)		<0.0010
•	Nickel (Ni)		0.0049
•	Copper (Cu)		0.0048
•	Aluminum (Al)		0.036
•	Tungsten (W)		0.019
•	Titanium (Ti)		<0.0002
•	Cobalt (Co)		0.0022
•	Vanadium (V)		0.0011
•	Ferrum (Fe)		99.67
Kết luận: Thành phần hóa học tương ứng mác thép SPHC			

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIẾN



GIÁM ĐỐC
DƯỜNG ĐÌNH THÔNG

CÔNG TY TNHH THẮNG LỢI
NHÀ MÁY ĐÚC THÉP HỢP KIM CAO VICO



Số: □□□.PT/VC

Địa chỉ : Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 05 tháng 03 năm 2021.

KẾT QUẢ THỬ NGHIỆM
TEST RESULT

AUGER TUBING

1. Tên mẫu/Sample: MẪU TÔN 1.6mm (04-03-2021)
2. Khách hàng/Customer: CÔNG TY MAI VĂN ĐĂNG
3. Kết quả/Results:

TT Items	Tên chi tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
▶	Carbon (C)		0.050
▶	Silicon (Si)		0.0095
▶	Manganese (Mn)		0.172
▶	Phosphorus (P)		0.0090
▶	Sulfur (S)		0.0014
▶	Chromium (Cr)		0.018
▶	Molybdenum (Mo)		0.0010
▶	Nickel (Ni)		0.012
▶	Copper (Cu)		0.023
▶	Aluminum (Al)		0.020
▶	Tungsten (W)		<0.0050
▶	Titanium (Ti)		<0.0002
▶	Cobalt (Co)		0.0029
▶	Vanadium (V)		<0.0005
▶	Ferrum (Fe)		99.68

Kết luận: Thành phần hóa học tương ứng mác thép SPHC

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIẾN



GIÁM ĐỐC
PHÙNG ĐÌNH THÔNG



CÔNG TY TNHH THĂNG LỢI
NHÀ MÁY ĐÚC THÉP HỢP KIM CAO VICO

Số: 01...PT/VIC

Địa chỉ: Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978.564.468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 9 tháng 01 năm 2021.

KẾT QUẢ THỬ NGHIỆM
TEST RESULT

1. Tên mẫu/Sample: MẪU ỐNG 19.1x2.3
2. Khách hàng/Customer: CÔNG TY MAI VĂN ĐĂNG
3. Kết quả/Results:

AUGERS - TIGA900

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
•	Carbon (C)		0.060
•	Silicon (Si)		0.0051
•	Manganese (Mn)		0.158
•	Phosphorus (P)		0.012
•	Sulfur (S)		0.0042
•	Chromium (Cr)		0.015
•	Molybdenum (Mo)		0.0022
•	Nickel (Ni)		0.0064
•	Copper (Cu)		0.0061
•	Aluminum (Al)		0.024
•	Tungsten (W)		0.010
•	Titanium (Ti)		0.0002
•	Cobalt (Co)		0.0012
•	Vanadium (V)		0.0009
•	Ferrum (Fe)		99.70
Kết luận: Thành phần hóa học tương ứng mác thép SS400			

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIẾN

PHÊ DUYỆT



GIÁM ĐỐC



NHA MAY ĐUC THEP HỢP KIM CAO VICO

Số: 0001..PT/VC

Địa chỉ: Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 9 tháng 01 năm 2021.

KẾT QUẢ THỬ NGHIỆM TEST RESULT

TIDKP - PLATES

1. Tên mẫu/Sample: MẪU TÔN 3.0mm
2. Khách hàng/Customer: CÔNG TY MAI VĂN DẮNG
3. Kết quả/Results:

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
▸	Carbon (C)		0.068
▸	Silicon (Si)		0.0088
▸	Manganese (Mn)		0.187
▸	Phosphorus (P)		0.0088
▸	Sulfur (S)		0.0033
▸	Chromium (Cr)		0.020
▸	Molybdenum (Mo)		0.0030
▸	Nickel (Ni)		0.0076
▸	Copper (Cu)		0.018
▸	Aluminum (Al)		0.031
▸	Tungsten (W)		0.013
▸	Titanium (Ti)		0.0007
▸	Cobalt (Co)		0.0018
▸	Vanadium (V)		0.0009
▸	Ferrum (Fe)		99.63
Kết luận: Thành phần hóa học tương ứng mác thép SPHC			

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIẾN

PHÊ DUYỆT



GIÁM ĐỐC

CÔNG TY TNHH THẮNG LỢI

NHÀ MÁY ĐÚC THÉP HỢP KIM CAO VICO



Số: □□□□.PT/VC

Địa chỉ : Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 16 tháng 01 năm 2021.

KẾT QUẢ THỬ NGHIỆM TEST RESULT

TIDKP - PLATES

1. Tên mẫu/Sample: MẪU TÓN 3.0mm
2. Khách hàng/Customer: CÔNG TY MAI VĂN ĐĂNG
3. Kết quả/Results:

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
▸	Carbon (C)		0.053
▸	Silicon (Si)		0.044
▸	Manganese (Mn)		0.165
▸	Phosphorus (P)		0.014
▸	Sulfur (S)		0.0070
▸	Chromium (Cr)		0.054
▸	Molybdenum (Mo)		<0.0010
▸	Nickel (Ni)		0.028
▸	Copper (Cu)		0.0093
▸	Aluminum (Al)		0.014
▸	Tungsten (W)		0.0054
▸	Titanium (Ti)		0.0012
▸	Cobalt (Co)		0.0081
▸	Vanadium (V)		0.0011
▸	Ferrum (Fe)		99.60
Kết luận: Thành phần hóa học tương ứng mức thép SPHC			

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIỀN

PHÊ DUYỆT



GIÁM ĐỐC
PHÙNG ĐÌNH THÔNG



SHOT ON REDMI 7
AI DUAL CAMERA



NHA MAY ĐUC THEP HỢP KIM CAO VICO

Số: 000..PT/VC

Địa chỉ : Số 5 - Đường N1 — CCN An Xá - Tp. Nam Định — Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 9 tháng 01 năm 2021.

KẾT QUẢ THỬ NGHIỆM TEST RESULT

POST SADDLE

1. Tên mẫu/Sample: MẪU TỖN 2.0mm
2. Khách hàng/Customer: CÔNG TY MAI VĂN ĐÁNG
3. Kết quả/Results:

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
▸	Carbon (C)		0.068
▸	Silicon (Si)		0.0052
▸	Manganese (Mn)		0.181
▸	Phosphorus (P)		0.017
▸	Sulfur (S)		0.0036
▸	Chromium (Cr)		0.030
▸	Molybdenum (Mo)		0.0013
▸	Nickel (Ni)		0.0075
▸	Copper (Cu)		0.0039
▸	Aluminum (Al)		0.025
▸	Tungsten (W)		0.016
▸	Titanium (Ti)		0.0003
▸	Cobalt (Co)		0.0026
▸	Vanadium (V)		0.0007
▸	Ferrum (Fe)		99.64
Kết luận: Thành phần hóa học tương ứng mác thép SPHC			

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIỀN

PHÊ DUYỆT



GIÁM ĐỐC

CÔNG TY TNHH THẮNG LỢI

NHÀ MÁY ĐÚC THÉP HỢP KIM CAO VICO



Số:PT/VC

Địa chỉ : Số 5 - Đường N1 - CCN An Xá - Tp. Nam Định - Nam Định

Tel: 0228.8606088 * Fax: 0228.3660671 * Mobi: 0978 564 468

Website: <http://luyenkim.net> * Email: thangloind@gmail.com

Nam Định, ngày 27 tháng 01 năm 2021.

KẾT QUẢ THỬ NGHIỆM TEST RESULT

1. Tên mẫu/Sample: MẪU TÔN 2.0mm
2. Khách hàng/Customer: CÔNG TY MAI VĂN ĐĂNG
3. Kết quả/Results:

POST SADDLE

TT Items	Tên chỉ tiêu Specification	Thiết bị kiểm tra Test machine	Kết quả Results
1	Thành phần hóa học Chemical compositions: %	Bruker Q4 Tasman	
<input type="checkbox"/>	Carbon (C)		0.067
<input type="checkbox"/>	Silicon (Si)		0.040
<input type="checkbox"/>	Manganese (Mn)		0.274
<input type="checkbox"/>	Phosphorus (P)		0.0057
<input type="checkbox"/>	Sulfur (S)		0.0029
<input type="checkbox"/>	Chromium (Cr)		0.063
<input type="checkbox"/>	Molybdenum (Mo)		0.0026
<input type="checkbox"/>	Nickel (Ni)		0.016
<input type="checkbox"/>	Copper (Cu)		0.014
<input type="checkbox"/>	Aluminum (Al)		0.051
<input type="checkbox"/>	Tungsten (W)		0.016
<input type="checkbox"/>	Titanium (Ti)		0.0025
<input type="checkbox"/>	Cobalt (Co)		0.0022
<input type="checkbox"/>	Vanadium (V)		0.0016
<input type="checkbox"/>	Ferrum (Fe)		99.44

Kết luận: Thành phần hóa học tương ứng mức thép SPHC

KIỂM ĐỊNH VIÊN

PHẠM QUANG HIẾN



GIÁM ĐỐC
PHÙNG ĐÌNH THỐNG

SHOT ON REDMI 7
AI DUAL CAMERA

APPENDIX C:
EQUIPMENT CALIBRATION
RECORDS



Report and Certificate of Calibration



www.Cal-Cert.com



Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620

Report #: 18579-82054-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-01315T / 01498 Load Cell Tovey Engineering SN: 119831A Cal: 02/09/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 291.00 - 10,000 lbf Report #: 17942-72939-1595

Instrument Data

Calibration Date: May 26, 2021	Normative Reference: ASTM E4-16
Recommended Due Date: May 26, 2022	Cal-Cert Procedure: CP-001
Calibration Frequency: 12 Months	Indicating System: Digital
Manufacturer: Optima Scale	Temperature: 75 °F
Type: Load Cell	Humidity: 37% RH
Model Number: OP-312	Cal Factor: None
Serial #: SVT2946	Asset #: Accredited
Capacity: 10,000 lbf.	Service Location: Service Address
Tolerance: ±1% of Applied Load	As Found: FAIL
Method of Calibration: Follow the Force	As Left: PASS

Calibration Data

Calibrated Range:		1000 to 9500 lbf.			Range Resolution:			1 lbf.		Mode Verified:		Tension
Unit Under Test Reading	Calibration Standard As Found	As Found Percentage Error	Verification Reading #1	Error	Percentage Error	Verification Reading #2	Error	Percentage Error	Algebraic Difference	Expanded Uncertainty		
lbf.	lbf.		lbf.	lbf.		lbf.	lbf.			lbf.		
0	0	0.0%	0	0	0.0%	0	0	0.0%	0.0%	0.00		
1,000	1011.4	1.14%	1002.3	2.3	0.23%	1001.4	1.4	0.14%	0.09%	4.00		
2,000	2022.5	1.13%	2008.0	8.0	0.40%	2007.2	7.2	0.36%	0.04%	4.70		
4,000	4044.4	1.11%	4017.3	17.3	0.43%	4016.8	16.8	0.42%	0.01%	6.80		
6,000	6071.8	1.20%	6019.1	19.1	0.32%	6023.7	23.7	0.39%	-0.08%	9.40		
8,000	8090.8	1.14%	8025.6	25.6	0.32%	8028.5	28.5	0.36%	-0.04%	12.10		
9,500.0	9607.5	1.13%	9531.8	31.8	0.33%	9531.9	31.9	0.34%	0.00%	14.20		
0	0	0.0%	0	0	0.0%	0	0	0.0%	0.0%	0.00		

Bold and Strikethrough indicates a Failed Reading.

Max Range Permissible Error Percentage: 0.43%

Manufacturer: Optima Scale

Type: Load Cell

Serial #: SVT2946

Remarks:

All force measurement standards utilized in this calibration are temperature compensated.

**We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs.
Cleaning and preventative maintenance were performed as part of this service.**

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01.
A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NC SL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above.

Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a $k=2$ for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated.

All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate.

This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer:

Joe Borszich

Date:

May 26, 2021

Technical Manager:

Marshall Doyle

Signature:



Report and Certificate of Calibration



www.Cal-Cert.com



Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620

Report #: 18579-82053-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-01315C / 01498 Load Cell Tovey Engineering SN: 119831A Cal: 02/09/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 200.00 - 10,000 lbf Report #: 17942-64237-1595

Instrument Data

Calibration Date:	May 26, 2021	Reference:	ASTM E-4
Recommended Due Date:	May 26, 2022	Cal-Cert Procedure:	CP-001
Calibration Frequency:	12 Months	Indicating System:	Computer
Manufacturer:	Tinius Olsen	Temperature:	64 °F
Type:	Torsion Testing Machine	Humidity:	51% RH
Model Number:	Electromatic	Cal Factor:	None
Serial #:	46286	Asset #:	Accredited
Capacity:	750000 in. lbf.	Service Location:	Service Address
Tolerance:	1.00% of Reading	As Found:	Pass
		As Left:	Pass

Instrument Range: 750,000 in. lbf.			Resolution: 1 in. lbf.			Mode Verified: Compression			
Unit Under Test Reading	As Found	Tolerance	Verification Reading #1	Error	Tolerance	Verification Reading #2	Error	Tolerance	Average Error
0	0	0	0	0	0	0	0	0	0
50000	50290	500.0	50290	290	500.0	49990	-10	500.0	140
100000	100390	1000.0	100390	390	1000.0	100140	140	1000.0	265
200000	200720	2000.0	200720	720	2000.0	200640	640	2000.0	680
300000	301690	3000.0	301690	1690	3000.0	301550	1550	3000.0	1620
400000	402550	4000.0	402550	2550	4000.0	402640	2640	4000.0	2595
500000	503610	5000.0	503610	3610	5000.0	503650	3650	5000.0	3630
600000	605310	6000.0	605310	5310	6000.0	605000	5000	6000.0	5155
750000	756990	7000.0	756990	6990	7000.0	756960	6960	7000.0	6975
0	0	0	0	0	0	0	0	0	0

Expanded Uncertainty ± 288.6876 in. lbf.

Manufacturer: Tinius Olsen

Type: Torsion Testing Machine

Serial #: 46286

Remarks:

Beam weight correction is 728.4 pounds at 100 inches mounted to the machine. Moment arm is 100 inches, sn: 46287. The machine reads torsion in both directions, the readings were taken in a clockwise rotation with the machine starting at the natural zero.
Tolerance is 1% of the reading taken.

**We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs.
Cleaning and preventative maintenance were performed as part of this service.**

**Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01.
A2LA is recognized under the ILAC mutual recognition agreement (MRA).**

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.1, and meets the requirements of all applicable references and Cal-Cert procedures listed above.
Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated.
All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate.

This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer:

Joe Borszich

Date:

May 26, 2021

Technical Manager:

Marshall Doyle

Signature:



Report and Certificate of Calibration



www.Cal-Cert.com



Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620

Report #: 18579-17117-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-01094C / 01498 Load Cell Tovey Engineering SN: 114638A Cal: 02/08/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 1,000.00 - 50,000 lbf Report #: 17942-32501-1595

Instrument Data


Calibration Date:	May 25, 2021	Reference:	ASTM E-4
Calibration Due Date:	May 25, 2022	Cal-Cert Procedure:	CP-001
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Bva	Temperature:	75 °F
Model Number:	H1006	Humidity:	23% RH
Type:	Hydraulic Ram	Cal Factor:	None
Serial #:	R0707000630/Pump P80	Asset #:	Accredited
Capacity:	5,000 PSI	Service Location:	Service Address
Resolution:	1 PSI	As Found:	Pass
Standard Units:	Lbf.	As Left:	Pass

Instrument Range:	5,000	Range Resolution:	2.206	Mode Verified:	Compression
--------------------------	-------	--------------------------	-------	-----------------------	-------------

High Range

UUT Reading	As Found Reading	Verification Reading #1	Verification Reading #2	Average Readings
PSI	Lbf.	Lbf.	Lbf.	Lbf.
0	0	0	0	0
1000	2138	2138	2182	2160
1500	3241	3241	3300	3271
2000	4369	4369	4442	4406
2500	5473	5473	5541	5507
3000	6600	6600	6660	6630
3500	7732	7732	7796	7764
4000	8876	8876	8930	8903
4500	9976	9976	10051	10014
5000	11121	11121	11166	11144

Expanded Uncertainty ± 2.8909 Lbf.



Remarks:

**We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs.
Cleaning and preventative maintenance were performed as part of this service.**

**Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01.
A2LA is recognized under the ILAC mutual recognition agreement (MRA).**

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.1, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated.

All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate.

This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer:

Joe Borszich

Date:

May 25, 2021

Technical Manager:

Marshall Doyle

Signature:

Report and Certificate of Calibration



www.Cal-Cert.com



Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620

Report #: 18579-17118-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-00136C / 01498 Load Cell Revere SN: 50379023 Cal: 02/16/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 14370.00 - 600,000 lbf Report #: 17942-32480-1595
01094C / 01498 Load Cell Tovey Engineering SN: 114638A Cal: 02/08/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 1,000.00 - 50,000 lbf Report #: 17942-32501-15

Instrument Data


Calibration Date:	May 25, 2021	Reference:	ASTM E-4
Calibration Due Date:	May 25, 2022	Cal-Cert Procedure:	CP-001
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Bva	Temperature:	77 °F
Model Number:	HC6003T	Humidity:	24% RH
Type:	Hydraulic Ram	Cal Factor:	None
Serial #:	S1112000056-1/Pump P80	Asset #:	Accredited
Capacity:	10,000 PSI	Service Location:	Service Address
Resolution:	1 PSI	As Found:	Pass
Standard Units:	Lbf.	As Left:	Pass

Instrument Range:	10,000	Range Resolution:	14.311	Mode Verified:	Compression
--------------------------	--------	--------------------------	--------	-----------------------	-------------

High Range

UUT Reading PSI	As Found Reading Lbf.	Verification Reading #1 Lbf.	Verification Reading #2 Lbf.	Average Readings Lbf.
0	0	0	0	0
1000	14330	14330	13910	14120
2000	28690	28690	28230	28460
3000	43050	43050	42860	42955
4000	57690	57690	57220	57455
5000	71950	71950	71660	71805
6000	86450	86450	86080	86265
7000	100870	100870	100210	100540
8000	115020	115020	114660	114840

Expanded Uncertainty ± **4.6215 Lbf.**



Remarks:

[Empty box for remarks]

**We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs.
Cleaning and preventative maintenance were performed as part of this service.**

**Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01.
A2LA is recognized under the ILAC mutual recognition agreement (MRA).**

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.1, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated.

All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate.

This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer:

Joe Borszich

Date:

May 25, 2021

Technical Manager:

Marshall Doyle

Signature:

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-1662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-17114-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-00969 Gage Block Set SPI SN: 7323 Cal: 02/19/2021 Due: 01/31/2023 Vendor: Precision Gage Report #: 17942-6105-5

Instrument Data

Calibration Date:	May 27, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 27, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	71 °F
Type:	Digital Dial Indicator	Humidity:	36% RH
Model Number:	Q2820-0-16	Asset #:	Accredited
Serial #:	140958038	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:	4.0000 Inches		Range Resolution:		0.0001 Inches	
	Calibration Standard	As Found	As Left Reading 1	As Left Reading 2	Tolerance Low	Tolerance High
	Inches	Inches	Inches	Inches	Inches	Inches
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.8000	0.8001	0.8001	0.8001	0.7997	0.8003
	1.5000	1.5000	1.5000	1.5001	1.4997	1.5003
	2.4000	2.4001	2.4001	2.4000	2.3997	2.4003
	3.2000	3.1998	3.1998	3.1998	3.1997	3.2003
	4.0000	3.9997	3.9997	3.9998	3.9997	4.0003
	3.2000	3.1999	3.1999	3.1999	3.1997	3.1999
	2.4000	2.4000	2.4000	2.4000	2.4000	2.4002
	1.5000	1.4999	1.4999	1.4999	1.4999	1.5001
	0.8000	0.8001	0.8001	0.8000	0.8000	0.8002
	0.0000	0.0000	0.0000	0.0000	-0.0001	0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs.
 Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01.
 A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above.
 Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated.
 All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate.
 This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Joe Borszich **Date:** May 27, 2021
Technical Manager: Marshall Doyle **Signature:**

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-182945-2874 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

7-00664 Gage Block Set SPI SN: 7252 / A1447 / A1502 / A1513 Cal: 09/29/2020 Due: 08/31/2022 Vendor: Cal-Cert Report #: 16037-32572-5
7-01450 Thermo-Hygrometer Comark SN: 06210350182 Cal: 10/01/2020 Due: 08/31/2021 Vendor: Cal-Cert Range: 122°F 95%RH Report #: 16037-86413-2363

Instrument Data

Calibration Date:	May 26, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 26, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	74 °F
Type:	Digital Dial Indicator	Humidity:	36% RH
Model Number:	Q2820-0-16	Asset #:	Accredited
Serial #:	200063407	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:	4.0000 Inches		Range Resolution:		0.0001 Inches	
	Calibration Standard Inches	As Found Inches	As Left Reading 1 Inches	As Left Reading 2 Inches	Tolerance Low Inches	Tolerance High Inches
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.8000	0.8001	0.8001	0.8000	0.7997	0.8003
	1.5000	1.5000	1.5000	1.5000	1.4997	1.5003
	2.4000	2.4000	2.4000	2.4000	2.3997	2.4003
	3.2000	3.2000	3.2000	3.2000	3.1997	3.2003
	4.0000	4.0000	4.0000	4.0000	3.9997	4.0003
	3.2000	3.2000	3.2000	3.2000	3.1999	3.2001
	2.4000	2.4000	2.4000	2.4000	2.3999	2.4001
	1.5000	1.5000	1.5000	1.5000	1.4999	1.5001
	0.8000	0.8000	0.8000	0.8000	0.8000	0.8002
	0.0000	0.0000	0.0000	0.0000	-0.0001	0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs. Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01. A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated. All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate. This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Samuel Fritkin **Date:** May 26, 2021
Technical Manager: Marshall Doyle **Signature:** *McDoyle*

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-182946-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-00069 Gage Block Set SPI SN: 7323 Cal: 02/19/2021 Due: 01/31/2023 Vendor: Precision Gage Report #: 17942-6105-5

Instrument Data

Calibration Date:	May 27, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 27, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	71 °F
Type:	Digital Dial Indicator	Humidity:	30% RH
Model Number:	Q2820-0-16	Asset #:	Accredited
Serial #:	200063410	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:	4.0000 Inches		Range Resolution:		0.0001 Inches	
	Calibration Standard	As Found	As Left Reading 1	As Left Reading 2	Tolerance Low	Tolerance High
	Inches	Inches	Inches	Inches	Inches	Inches
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.8000	0.8002	0.8002	0.8001	0.7997	0.8003
	1.5000	1.4999	1.4999	1.5000	1.4997	1.5003
	2.4000	2.3998	2.3998	2.3999	2.3997	2.4003
	3.2000	3.1997	3.1997	3.1998	3.1997	3.2003
	4.0000	3.9998	3.9998	3.9997	3.9997	4.0003
	3.2000	3.1998	3.1998	3.1997	3.1996	3.1998
	2.4000	2.3997	2.3997	2.3998	2.3997	2.3999
	1.5000	1.4999	1.4999	1.4999	1.4999	1.5001
	0.8000	0.8001	0.8001	0.8002	0.8001	0.8003
	0.0000	0.0000	0.0000	0.0000	-0.0001	0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs. Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01. A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated. All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate. This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Joe Borszich **Date:** May 27, 2021
Technical Manager: Marshall Doyle **Signature:** *McDoyle*

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-22274-28 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

1-00065 Thermo-Hygrometer Comark SN: 06217150042 Cal: 02/12/2021 Due: 01/31/2022 Vendor: Cal-Cert Range: 95 %RH 122 °F Report #: 17942-32477-318
1-00969 Gage Block Set SPI SN: 7323 Cal: 02/19/2021 Due: 01/31/2023 Vendor: Precision Gage Report #: 17942-6105-5

Instrument Data

Calibration Date:	May 27, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 27, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	71 °F
Type:	Digital Dial Indicator	Humidity:	36% RH
Model Number:	02820-0-16	Asset #:	Accredited
Serial #:	122416189	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:		4.0000 Inches		Range Resolution:		0.0001 Inches	
Calibration Standard	As Found	As Left Reading 1	As Left Reading 2	Tolerance Low	Tolerance High		
Inches	Inches	Inches	Inches	Inches	Inches		
0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000
0.8000	0.7999	0.7999	0.8000	0.7997	0.8003		0.8003
1.5000	1.4998	1.4998	1.4999	1.4997	1.5003		1.5003
2.4000	2.4000	2.4000	2.3999	2.3997	2.4003		2.4003
3.2000	3.1999	3.1999	3.2000	3.1997	3.2003		3.2003
4.0000	4.0000	4.0000	3.9999	3.9997	4.0003		4.0003
3.2000	3.2000	3.2000	3.1999	3.1999	3.2001		3.2001
2.4000	2.3999	2.3999	2.3999	2.3999	2.4001		2.4001
1.5000	1.4999	1.4999	1.4998	1.4997	1.4999		1.4999
0.8000	0.8000	0.8000	0.7999	0.7999	0.8001		0.8001
0.0000	0.0000	0.0000	0.0000	-0.0001	0.0001		0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs. Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01. A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated. All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate. This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Joe Borszich **Date:** May 27, 2021
Technical Manager: Marshall Doyle **Signature:** *McDoyle*

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-1662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-81546-2874 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

7-00664 Gage Block Set SPI SN: 7252 / A1447 / A1502 / A1513 Cal: 09/29/2020 Due: 08/31/2022 Vendor: Cal-Cert Report #: 16037-32572-5
7-01450 Thermo-Hygrometer Comark SN: 06210350182 Cal: 10/01/2020 Due: 08/31/2021 Vendor: Cal-Cert Range: 122°F 95%RH Report #: 16037-86413-2363

Instrument Data

Calibration Date:	May 26, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 26, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	71 °F
Type:	Digital Dial Indicator	Humidity:	38% RH
Model Number:	Q2820-0-16	Asset #:	Accredited
Serial #:	172194728	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:		4.0000 Inches		Range Resolution:		0.0001 Inches	
Calibration Standard	As Found	As Left Reading 1	As Left Reading 2	Tolerance Low	Tolerance High		
Inches	Inches	Inches	Inches	Inches	Inches		
0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000
0.8000	0.8000	0.8000	0.8000	0.8000	0.7997		0.8003
1.5000	1.5000	1.5000	1.5000	1.5000	1.4997		1.5003
2.4000	2.4001	2.4001	2.4001	2.4001	2.3997		2.4003
3.2000	3.2000	3.2000	3.2000	3.2000	3.1997		3.2003
4.0000	4.0000	4.0000	4.0000	4.0000	3.9997		4.0003
3.2000	3.2000	3.2000	3.2000	3.2000	3.1999		3.2001
2.4000	2.4001	2.4001	2.4001	2.4001	2.4000		2.4002
1.5000	1.5000	1.5000	1.5000	1.5000	1.4999		1.5001
0.8000	0.8000	0.8000	0.8000	0.8000	0.7999		0.8001
0.0000	0.0000	0.0000	0.0000	0.0000	-0.0001		0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs. Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01. A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated. All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate. This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Samuel Fritkin **Date:** May 26, 2021
Technical Manager: Marshall Doyle **Signature:** *McDoyle*

Report and Certificate of Calibration



www.Cal-Cert.com

Toll Free
800-356-4662

Address
6709 SE Lake Road
Milwaukie, OR 97222

Local
503-654-9620



Report #: 18579-182947-2874 **Customer PO#:**
Customer Name: CTL Thompson
Customer Address: 400 North Link Lane
City: Fort Collins **State:** CO **Zip:** 80524
Contact: Craig Ellis
Service Address: 400 North Link Lane Fort Collins, CO 80524

Calibration Standards

7-00664 Gage Block Set SPI SN: 7252 / A1447 / A1502 / A1513 Cal: 09/29/2020 Due: 08/31/2022 Vendor: Cal-Cert Report #: 16037-32572-5
7-01450 Thermo-Hygrometer Comark SN: 06210350182 Cal: 10/01/2020 Due: 08/31/2021 Vendor: Cal-Cert Range: 122°F 95%RH Report #: 16037-86413-2363

Instrument Data

Calibration Date:	May 26, 2021	Reference:	ASME B89.1.10M
Calibration Due Date:	May 26, 2022	Cal-Cert Procedure:	CP-009
Calibration Frequency:	12 Months	Indicating System:	Digital
Manufacturer:	Humboldt	Temperature:	72 °F
Type:	Digital Dial Indicator	Humidity:	38% RH
Model Number:	Q2820-0-16	Asset #:	Accredited
Serial #:	200063409	Service Location:	Service Address
Capacity:	4 Inches	As Found:	PASS
Resolution:	0.0001 Inches	As Left:	PASS

Instrument Range:		4.0000 Inches		Range Resolution:		0.0001 Inches	
Calibration Standard	As Found	As Left Reading 1	As Left Reading 2	Tolerance Low	Tolerance High		
Inches	Inches	Inches	Inches	Inches	Inches		
0.0000	0.0000	0.0000	0.0000	0.0000	0.0000		0.0000
0.8000	0.8000	0.8000	0.8000	0.8000	0.7997		0.8003
1.5000	1.5000	1.5000	1.5000	1.5000	1.4997		1.5003
2.4000	2.4000	2.4000	2.4000	2.4000	2.3997		2.4003
3.2000	3.2000	3.2000	3.2000	3.2000	3.1997		3.2003
4.0000	4.0000	4.0000	4.0000	4.0000	3.9997		4.0003
3.2000	3.2000	3.2000	3.2000	3.2000	3.1999		3.2001
2.4000	2.4000	2.4000	2.4000	2.4000	2.3999		2.4001
1.5000	1.5000	1.5000	1.5000	1.5000	1.4999		1.5001
0.8000	0.8000	0.8000	0.8000	0.8000	0.7999		0.8001
0.0000	0.0000	0.0000	0.0000	0.0000	-0.0001		0.0001

Expanded Uncertainty ± 0.00014 Inches

Remarks:

We sincerely thank you for your business. Please call us at 503-654-9620 for all your sales and calibration needs. Cleaning and preventative maintenance were performed as part of this service.

Cal-Cert is accredited by A2LA under Calibration Laboratory Code #4986.01. A2LA is recognized under the ILAC mutual recognition agreement (MRA).

This certificate is hereby issued that the above instrument was tested for accuracy with calibrated standards traceable to the National Institute of Standards and Technology (NIST). The information provided on this form complies with the data gathering and reporting requirements of ISO/IEC 17025 and ANSI/NCSL Z540.3, and meets the requirements of all applicable references and Cal-Cert procedures listed above. Any stated measurement uncertainty includes the uncertainty of the Calibration standards used, combined with the uncertainty of the measurement process using the RSS method with a k=2 for an approximate 95% level of confidence. The calibration process meets or exceeds a ratio of 4:1 unless otherwise stated. All tolerances were derived from the applicable standards and pass/fail determination is based on those tolerances. The customer determined any recommended due dates indicated on the certificate. This report shall not be reproduced except in full, without written approval from Cal-Cert.

Service Engineer: Samuel Fritkin **Date:** May 26, 2021
Technical Manager: Marshall Doyle **Signature:** *Mr Doyle*