## INFO@CARAVANSAWAYCOM.AU | WWW.CARAVANSAWAY.COM.AU

## PRE-TRIP RV CHECKLIST

	Doors & cupboards - closed and locked
	No heavy items stored in overhead cabinets
(	Counter tops - Cleared
4	All lose items - secured
	TV & antenna - TV removed or in travel position
	Wind down TV antenna and secure
	Fridge - locked, set to 12V mode & engage the travel catch.
	/ents / hatches/ skylights/ windows/ stone shields-
	Close and lock
	Taps and shower control - turned off
	12V master switch - turned off
	Kept on if you need your fridge on
	If kept on, turn off lights at their switches & unplug appliance
	Mains power supply - Isolate
	Main door and lockers - closed and locked
	Entrance step - Retracted and locked in position
	Awnings - Rolled up and locked in the travel position
	<b>Mirrors</b> - Fixed, clean & adjusted
	Cords- Water, sullage and electrical cords disconnected



## INFO@CARAVANSAWAYCOM.AU | WWW.CARAVANSAWAY.COM.AU

## PRE-TRIP RV CHECKLIST

(	Gas taps & cylinders - turned off and properly secured
\	Water systems & tanks - drained and pump turned off
] ]	Tyre tread and preassure - Check
١	Wheel fixing bolts - Tourques check
L	Lights - Connected (tow) & operation checked
E	Breaks - operational. Tow: emergency break cable connected
F	Fixing nuts on tow balls (tow) - Check
1	Noseweight (tow) - Check
E	Breakaway & safety cables (tow) - Attached
N	Motor mover (tow) - Disengaged
J	ockey wheel (tow) - Raised and secured
S	Stabilizers (tow): front and rear retracted in the up position
1	Trailer Hand break (tow) - correctly released
1	12V power lead for caravan lights: must be correctly
C	connected and the towing aids or level rides must be correctly
C	connected and adjusted.
S	Safety chains: correctly connected between the caravan and
_	<b>Pop-top caravans:</b> lower roof/ walls & lock with hinges

