

5037 Hanover Circle Cypress, CA 90630 800-509-0597 www.triactiveusa.com

Installation Sheet

Option A: (Most Common) Surface Mount – minimum installation requirements.

Overview: The equipment is surface mountable and is usually secured into concrete, installed footings, or existing slabs.

Customer Service: When planning an installation our customer service staff can answer any questions you might have about the process. We DO NOT do installations in-house, but our staff can direct you to companies in your area that can.

Planning: We can provide 3-D plans for your potential installation upon request. These proposed sample layouts are developed with your input with dimensions, site elements, etc.

Shipment: Once equipment has been delivered, please unwrap and inspect for damage BEFORE the shipping company departs. Please inform us of any damages ASAP.

Installation Clearance: 6 ft. cleared use zone surrounding each piece of equipment is typical.

Typical Installation: The easiest installations occur on existing concrete. Each piece of equipment has mounting tabs that are bolted to a concrete pad with a 3/8" anchor bolt, which are provided by others. **TriActive USA only provides the plastic security base and cap.**

Installation tools for existing concrete slabs: concrete hammer drill, 3/8" dia. Concrete drill bit, 3/8" x 3.5" concrete anchor bolts, steel hammer, ratchet and socket wrench kit, felt marker, and possibly a hand held hammer.

