## FALLTECH®

## 6036018

## SteelGrip® Temporary Cable HLL System and Stanchions with 18" beam clamps

## Features :

- Complete 60' Single-span Temporary Cable HLL System
- Includes two I-beam stanchions with 4" to 18" clamping range.
- 3/8" galvanized steel cable with one-end terminated and thimbled
- Features 1 stainless steel coil energy absorber and 2 connecting carabiners
- In-line tension indicator included with 2 galvanized steel shackles
- System also includes wire rope clips and tensioning turnbuckle
- Cable HLL System meets OSHA 1926.502 and 1910.140 regulations



Material Specifications		Performance Specifications		Compliant With:	
Cable	3/8" galvanized steel; 5,000 lb min. static strength	Static Strength	5,000 lb min.	Cable	HLL System meets OSHA 1926.502 and 1910.140 regulations
			310 lb max. per user; 2 users max. per single span		
Stanchions	Plated carbon steel post, base and clamp; 8,000 lb min. static strength	OSHA User Capacity			
Carabiners	Plated alloy steel; 5,000 lb min. static strength with 3,600 lb gate strength				

Sizes & Part Numbers					
6033018 -	6036018 -	6038018 -	60310018 -		
30'	60'	80'	100'		