Air Cleaner Test Report

Applicant : RHT Industries Limited

Address : Block B, 2/F, Goodwill Industrial Building, No. 36-44 Pak Tin Par

Street, Tsuen Wan, New Territories, Hong Kong

Application Number : KJ2306001-6

Report Number : REPAP23060601

Report Issue Date : 13 Jun 2023

Total Page : 8 Pages (including this page)

This document is issued by the Company under its General Conditions of Service printed overleaf. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any older of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to fullest extent of the law.

Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30days only. This document cannot be reproduced except in full, without prior approval of the Company.

TABLE OF CONTENT

1.	Sample Description	3
2.	Detail Description of the sample	4
3.	Testing Environment	5
4.	Testing Method of Removal Efficiency	6
5.	Result of Removal Efficiency	7 – 8

Acron International Technology Limited

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology under the Entrepreneurship Program

> Page 2 of 8 Report No.: REPAP23060601

1. Sample Description

Product : Air Cleaner

Brand Name : b-MOLA

Model No. : BP100

No. of Sample Received : 1

Test Date : 6 May 2023 – 6 May 2023

Test Item(s) : Pollutants Removal Efficiency

Test Requested : Ammonia

Test Reference(s) : In-house method SOP200 (for VOC removal rate)

Test Equipment : Honeywell instrument ppbRAE 3000

Equipment no. : E002 - 001

Test Result : See the attached sheets

Remark : N/A

Report No.: REPAP23060601

2. Detail Description of the sample





b-MOLA/BP100



NCCO Reactor (NA213020300) and Normal HEPA

Acron International Technology Limited

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology under the Entrepreneurship Program


Testing Environment

: 25.1°C Temperature

Relative Humidity : 51%

Testing Chamber : 1m³ Testing Chamber

Size $(W \times H \times D)$ mm : $1000 \times 100 \times 1000$



1m³ Testing Chamber

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology under the Entrepreneurship Program

Page 5 of 8 Report No.: REPAP23060601

Acron International Technology Limited Your Technical Companion **HKUST Entrepreneur**

Testing Method of Removal Efficiency

In a 1m3 chamber, chemical was injected into the chamber by a syringe and evaporated by a

hot plate. Internal circulation was turned on throughout the test to ensure the uniformity of

chemical concentration inside the chamber. Initial concentration (C₀) of the chemical was

recorded before switching on the air cleaner with a range of 100 (±10) mg/m³. Then, the air

cleaner is switched on for 60 minutes and the chemical concentration was recorded as C₆₀, the

final concentration of chemical.

The test was repeated without the air cleaner to determine the natural decay of the chemical

at the test chamber. Chemical was injected into the chamber by a syringe and evaporated by a

hot plate with an initial concentration (C_{N0}). The final concentration (C_{N60}) was determined 60

minutes later

New filters and HEPA have been used for each chemical test.

Acron International Technology Limited

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology

under the Entrepreneurship Program

Page 6 of 8

Report No.: REPAP23060601

5. Results of Removal Efficiency

Brand/ Model No.	Operation Mode	Test Chemical	Volume of use
			(mL)
b-MOLA/ BP100	SS	Ammonia	4.1

Initial Concentration	Natural Decay, kn	Total Decay, ke	Removal Efficiency	
(mg/m^3)	(min ⁻¹)	(min ⁻¹)	(%)	
109.8	0.001	0.128	>99.9	

Remark: Initial concentration is set within 100±10mg/m³.




Figure a. Natural Decay of Ammonia

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology under the Entrepreneurship Program




Figure b. Total Decay of Ammonia

Calculation:

$$A_{1} = \cfrac{C_{0} - C_{60}}{C_{0}}$$

$$A_{2} = \cfrac{C_{N0} - C_{N60}}{C_{N0}}$$

$$C_{0}(1 - A_{2}) - C_{60}$$
 Removal Efficiency =
$$\cfrac{C_{0}(1 - A_{2})}{C_{0}(1 - A_{2})}$$

A₁: Removal rate (%)
A₂: Natural decay rate (%)
C: Concentration of testing subject (mg/m³)

*** End of Report ***

Acron International Technology Limited

IAQ Contractor, IAQ Control Facilities Supplier, IAQ Consultant Subsidiary company of the Hong Kong University of Science and Technology under the Entrepreneurship Program

Page 8 of 8 Report No.: REPAP23060601