

## Code Compliance C405.2.2


**Timeswitch Controls** 


Occupancy Sensor Controls C405.2.1

C405.3 **Light Reduction Control** 

C405.2.6 Manual Controls

C405.11 Automatic Receptacle Control





## Sequence of Operations Example:

- 1. Manual light on via wall switch
- 2. Auto-off via OCC Sensor
- 3. Plug Load Control via Sensors/OCC
- 4. Light Reduction via DL Sensor
- 5. Multi Zones/Groups/Scenes

## Design Considerations

- 1. Wireless Switch & Sensor available for Retro Fit
- 2. Room can be fully networked with other Casambi Devices /Rooms
- 3. See knowledge base for setting up daylighting

