

# Mini Split Air Conditioning Installation Kit

**16 ft. Insulated Copper Line Set 1/4" × 1/2"**

## A-FP2416NS

Suitable Mini Split Capacity : Max. 9000 BTU

| <b>Copper Line (OD)</b> |                   |
|-------------------------|-------------------|
| Liquid Line 1/4"        | Suction Line 1/2" |

UL94 HF-1 Fire Retardant 3/8" Thick Insulation Foam  
Compliance with ASTM B280 Standard



## Installation Kit Includes

- 16 ft. Insulated Copper Line Set 1/4" × 1/2" with Flared Fittings
- 18 ft. Communication Wire
- 18 ft. Condensate Drain Hose
- Wall Sleeve Cylinder
- Wall Cap
- HVAC Putty
- Line Set Wrapping Tape

### Important Notice

• The insulated copper line set is shipped with sealed caps after cleaning the interior of the tube. Please remove the caps immediately before connection. If they are removed prematurely, dust, oil, water, or other debris may enter the tube and reduce the refrigerant capacity.

• The line set wrapping tape is designed for outdoor use to protect the line set from the elements while being easy to apply and remove without causing damage.

Tips:

1. Tape should be pulled tight while guiding it around the line set and overlapping half of the layer of tape below with each turn.
2. Avoid overstretching to prevent air bubbles.
3. Wrapping the tape from the bottom towards the top ensures that the tape is stacked on the bottoms so rainwater will not penetrate as easily. If the tape is wound from top to bottom, rainwater can penetrate through the gaps between the tapes, causing the line set to be exposed to moisture and may result in damage.
4. When finished wrapping, please be sure to press the tape down firmly to ensure a tight seal.