

SOLAER SB-2.3 FOR PONDS AND LAKES UP TO 3 ACRES

- Aerates Ponds/Lakes Where No Electricity Is Available
- Average 20 Hours Of Run Time Day And Night
- Battery Back-Up For Cloudy Conditions
- Improves Water Clarity & Quality
- Oxygenates Entire Water Column





Solaer® SB-2.3 Cabinet Interior

Product Details Aeration System

| Item Number | SB-2.3 |
|---|------------------|
| Maximum Pond Size | Up To 3 Acres |
| EcoFlow [™] 24V Compressor | 2 |
| Duraplate™ Diffusers | 3 |
| Maximum Diffuser Depth | 25 Feet |
| EcoFlow [™] Compressor | 48 Watts |
| Solar Panel w/Mounting Bracket | 2-24 Volt Panels |
| Max CFM | Up To 2.0 |
| 12V Deep Cycle AGM 115 AH Batteries Alpine™ | 4 |
| ½" Weighted Airline | Not Included |
| 3" Schedule 40 Mounting Pole (Required) | Not Included |
| Programmable Timer | 1 |
| Manifold | 2-2 Port |
| Cooling Fan | 1 |
| Level-Aer™ Equipment Pad (Suggested) | Not Included |
| Decibels/Operational Sound | 50/60 DB |
| Warranties | |

| waitaities | |
|--------------------------------------|----------|
| Complete Product Warranty | 2 Years |
| EcoFlow™ 24V Compressor | 2 Years |
| Alpine™ ½" Weighted Airline Warranty | Lifetime |
| Cabinet Warranty | 2 Years |
| Duraplate™ Diffuser | Lifetime |

Product Dimensions/Measurement

| Cabinet | 40" x 24" x 24" |
|-----------------------------|-----------------|
| Alpine™ ½" Weighted Airline | 1/2" ID x 1" OD |
| Level-Aer™ Equipment Pad | 30"x 42"x 3" |

^{*}Purchase (at least) an 8' long Schedule 40 steel pipe in the appropriate diameter for your system. Refer to top pole mount instructions. Longer pipe may be required in areas with very heavy snow fall. Dig 9"-12" in diameter hole with post hole digger. Secure pipe vertically in the ground with concrete; make sure it is plumb in all directions. Allow concrete to cure for 24 hours before mounting solar panel.

Solaer® 2.3