


# Heathland

Heathland combines natural weathered character with the performance of a machine-made tile in an attractive and cost-effective roofing product.

## KEY ADVANTAGES

- Concrete tile with randomly applied fine sand coating
- Varying hanging length
- Offers practical and economic alternative to handmade clay tiles



## PRODUCT DETAILS

<b>Size</b> (overall)	264 x 165mm
<b>Minimum Pitch</b>	35°
<b>Maximum Pitch</b> (subject to fixing specification)	90°
<b>Minimum Headlap</b>	Below 90° 65mm / at 90° 35mm
<b>Maximum Headlap</b>	88mm
<b>Minimum Gauge/Batten Spacing</b>	88mm
<b>Maximum Gauge/Batten Spacing</b>	below 90° 100mm / at 90° 115mm
<b>Hanging Length</b> (approx.)†	244mm
<b>Cover</b> (all figures are net and do not allow for wastage)‡	
Linear cover of 1 tile	165mm
Covering capacity	below 90° 60 tiles/m <sup>2</sup> / at 90° 52 tiles/m <sup>2</sup>
<b>Weight</b>	below 90° 75kg/m <sup>2</sup> / at 90° 65kg/m <sup>2</sup>
per pallet, including pallet (approx.)	1.01 tonnes
per 1000	1.25 tonnes
<b>Battens Required</b> (at max. gauge)	below 90° 10.0m/m <sup>2</sup>
<b>Batten Size</b>	
Rafter centres up to 600mm	38 x 25mm
<b>Fixing Clips</b>	Top Tile Clips
<b>Nail Size for Tiles**</b>	40 x 2.65mm (A/A)
<b>Pallet Quantities</b>	Tiles per pallet 768 / Tiles per pack 16 / Packs per pallet 48

\*All weights nominal \*\* (A/A) Aluminium Alloy

## FITTINGS & ACCESSORIES

### ORNAMENTAL TILE

Club Tiles

### ANGLES

External Angles

### HIP PRODUCTS

Universal Bonnet Hip  
Third Round Hip  
Baby Ridge  
Dry Hip  
Rapid Hip

### VALLEY PRODUCTS


Universal Valley Tile  
GRP 125 Valley  
Dry Valley

### RIDGE PRODUCTS

Half Round Ridge  
Half Round Monoridge

### VENTILATION SYSTEMS

RedVent EavesVent  
RedVent 25 Over-Fascia Vent  
Rapid EavesVent  
Top Edge Abutment Ventilation  
DryVent Ridge  
DryVent Monoridge  
Rapid Vented Ridge  
Uni-Vent Rapid Ridge/Hip  
RedLine Ventilation Tile



20 Manor House Mix (Sanded) 22 Wealden Red (Sanded) 23 Autumn (Sanded) 25 Ember (Sanded) 26 Elizabethan (Sanded)



# Heathland Product Codes

TILES		ABUTMENT PRODUCTS	
Standard Tile (shown above)	6661	Wakaflex Rapid Flashing	
Eaves/Top Tile	6664	Top Edge Abutment Ventilation Pack (3m)	9548
Tile-and-a-half	6669	Bonding Gutter (3m)	9578
UNDERLAYS		RIDGE PRODUCTS	
Spiritech 400 2S underlay	9202	DryVent Ridge (2.7m)	9058
Divoroll Elite 2S	9157	Uni-Vent Rapid Ridge/Hip (10m)	9313
Divoroll Universal 2S	9156	Continuous Ridge (5m)	9302
EAVES PRODUCTS		Half Round Ridge	7690
RedVent EavesVent 350-450mm (6m)	9189	DryVent Monoridge (2.7m)	9084
RedVent EavesVent 450-600mm (6m)	9190	Half Round Monoridge	7683
Extension Trays 350-450mm (6m)	9498	Mortar Bedded Fixing Kit	9314
Extension Trays 450-600mm (6m)	9499	VENTILATION TILES	
Rapid EavesVent 2-in-1 Tray	9988	RedLine Plain Tile Vent	9119
Rapid EavesVent Rafter Roll (6m)	9984	RedLine Vent Adaptor	9175
RedVent 25 Over-Fascia Vent (6m)	9593	Flexible Pipe (100 to 100mm)	9172
Underlay Support Tray (1.5m)	9076	EXTERNAL VERTICAL ANGLES	
Eaves Comb Filler (1m)	9965	External Angle 90° LH	7673
HIP PRODUCTS		External Angle 90° RH	7674
Dry Hip (2.7m)	9047	FIXING	
Continuous Hip (5m)	9524	Tile Nail (1596)	9331
Uni-Vent Rapid Ridge/Hip (10m)	9313	Top Tile Clip	9282
Uni-Vent Rapid Hip Support Tray (1.2m)	9069	Kro-Clip (50)	9142
Third Round Hip/Ridge Junction	9521		
Bonnet Hip Tile 35° - 50°	7671		
Third Round Hip (without nail holes)	7686		
Third Round Hip (with nail holes)	7687		
Hip Iron	9258		
Third Round Hip Block-End	7688		
Baby Ridge	7675		
Mortar Bedded Fixing Kit	9314		
VALLEY PRODUCTS			
GRP 125 Valley (3m)	9595		
Dry Valley (Low Profile)(3m)	9574		
Valley Tile 35° - 50°	7672		

BMI UK & Ireland  
 BMI House,  
 2 Pitfield, Kiln Farm,  
 Milton Keynes, MK11 3LW  
 +44 (0) 3705 601000

[www.bmigroup.com/uk](http://www.bmigroup.com/uk)

We are committed to continuously enhancing and improving our product range. We reserve the right to change our product specifications. We reserve the right to correct any typographical or clerical error or omission. For the latest information contact customer service.