

Products: **Liquid Rubber A-205**

Application: **Metal Roof Waterproofing**

Applicator: **Liquid Rubber Applicator**

Location: **Swift Current, SK**

Project size: **20,000 sq. ft.**

Completion date: **Summer 2015**

PROJECT DESCRIPTION

A small community Ice Arena leaked for years and years. The users got used to the drips until they learned of a solution that fit within their budget to become leak free.



LEAKING ICE ARENA



PREPPING



COMPLETED PROJECT

CHALLENGE

Prep and cleaning were most important to provide a sound substrate for the Liquid Rubber System.

LIQUID RUBBER SOLUTION

The roof structure was first cleaned of any contamination and loose rust.

Fasteners were tightened and/or replaced, then sealed with a brush application of HighBuild S-200.

Liquid Rubber Seam Tape bridged joints, gaps, seams, skylights, protrusions...

2 coats of Liquid Rubber A-205 were applied to achieve a final dry film thickness of 30 mil.