

Parts Tool

Category:

10 WALL FRAMING ▾

 Category Editor

 Save Sub-headings

Preliminary Text:



Formal Text:



Subcontractor Text:



| Category  | Description   | Cost   |     | Unit Type | Hrs/Unit | HLR              | Mat. Mult. | Code #     |   |
|---|---|--------|-----|-----------|----------|------------------|------------|------------|---|
|  10 WALL FRAMING   | Install 2" x 4", 12"oc, wood frame wall, up to 8' tall  | \$0.81 | per | Sq. Foot  | 0.024    | CARP 34.55 \$/hr | 1.000      | RM10401410 |       |
|  10 WALL FRAMING   | Install 2" x 4", 16"oc, wood frame wall, up to 8' tall  | \$0.66 | per | Sq. Foot  | 0.021    | CARP 34.55 \$/hr | 1.000      | RM10401610 |       |
|  10 WALL FRAMING   | Install 2" x 4", 24"oc, wood frame wall, up to 8' tall  | \$0.51 | per | Sq. Foot  | 0.018    | CARP 34.55 \$/hr | 1.000      | RM10401810 |       |
|  10 WALL FRAMING   | Install 2" x 4", 16"oc, wood frame wall, up to 8' tall  | \$0.84 | per | Sq. Foot  | 0.021    | CARP 34.55 \$/hr | 1.000      |            |       |
|  10 WALL FRAMING   | Install 2" x 4", 16"oc, wood frame wall, up to 8' tall  | \$0.84 | per | Sq. Foot  | 0.021    | CARP 34.55 \$/hr | 1.000      |            |       |
|  10 WALL FRAMING  | Install 2" x 4", 12"oc, wood frame wall, up to 10' tall | \$0.78 | per | Sq. Foot  | 0.020    | CARP 34.55 \$/hr | 1.000      | RM10402210 |     |
|  10 WALL FRAMING | Install 2" x 4", 16"oc, wood frame wall, up to 10' tall | \$0.63 | per | Sq. Foot  | 0.018    | CARP 34.55 \$/hr | 1.000      | RM10402410 |   |
|  10 WALL FRAMING | Install 2" x 4", 24"oc, wood frame wall, up to 10' tall | \$0.48 | per | Sq. Foot  | 0.015    | CARP 34.55 \$/hr | 1.000      | RM10402610 |   |
|  10 WALL FRAMING | Install 2" x 4", 12"oc, wood frame wall, up to 12' tall | \$0.74 | per | Sq. Foot  | 0.017    | CARP 34.55 \$/hr | 1.000      | RM10403010 |   |
|  10 WALL FRAMING | Install 2" x 4", 16"oc, wood frame wall, up to 12' tall | \$0.60 | per | Sq. Foot  | 0.015    | CARP 34.55 \$/hr | 1.000      | RM10403210 |   |
|  10 WALL FRAMING | Install 2" x 4", 24"oc, wood frame wall, up to 12' tall | \$0.45 | per | Sq. Foot  | 0.012    | CARP 34.55 \$/hr | 1.000      | RM10403410 |   |
|  10 WALL FRAMING | Install 2" x 6", 12"oc, wood frame wall, up to 8' tall  | \$1.22 | per | Sq. Foot  | 0.026    | CARP 34.55 \$/hr | 1.000      | RM10403810 |   |
|  10 WALL FRAMING | Install 2" x 6", 16"oc, wood frame wall, up to 8' tall  | \$0.99 | per | Sq. Foot  | 0.024    | CARP 34.55 \$/hr | 1.000      | RM10404010 |   |
|  10 WALL FRAMING | Install 2" x 6", 24"oc, wood frame wall, up to 8' tall  | \$0.76 | per | Sq. Foot  | 0.021    | CARP 34.55 \$/hr | 1.000      | RM10404210 |   |
|  10 WALL FRAMING | Install 2" x 6", 12"oc, wood frame wall, up to 10' tall | \$1.16 | per | Sq. Foot  | 0.022    | CARP 34.55 \$/hr | 1.000      | RM10404610 |   |
|  10 WALL FRAMING | Install 2" x 6", 16"oc, wood frame wall, up to 10' tall | \$0.94 | per | Sq. Foot  | 0.020    | CARP 34.55 \$/hr | 1.000      | RM10404810 |   |
|  10 WALL FRAMING | Install 2" x 6", 24"oc, wood frame wall, up to 10' tall | \$0.71 | per | Sq. Foot  | 0.017    | CARP 34.55 \$/hr | 1.000      | RM10405010 |   |
|  10 WALL FRAMING | Install 2" x 6", 12"oc, wood frame wall, up to 12' tall | \$1.13 | per | Sq. Foot  | 0.020    | CARP 34.55 \$/hr | 1.000      | RM10405410 |   |
|  10 WALL FRAMING | Install 2" x 6", 16"oc, wood frame wall, up to 12' tall | \$0.90 | per | Sq. Foot  | 0.017    | CARP 34.55 \$/hr | 1.000      | RM10405610 |   |
|  10 WALL FRAMING | Install 2" x 6", 24"oc, wood frame wall, up to 12' tall | \$0.67 | per | Sq. Foot  | 0.014    | CARP 34.55 \$/hr | 1.000      | RM10405810 |   |
|  10 WALL FRAMING | Install 2" x 8", 12"oc, wood frame wall, up to 8' tall  | \$1.71 | per | Sq. Foot  | 0.030    | CARP 34.55 \$/hr | 1.000      | RM10406210 |   |
|  10 WALL FRAMING | Install 2" x 8", 16"oc, wood frame wall, up to 8' tall  | \$1.38 | per | Sq. Foot  | 0.026    | CARP 34.55 \$/hr | 1.000      | RM10406410 |   |
|  10 WALL FRAMING | Install 2" x 8", 24"oc, wood frame wall, up to 8' tall  | \$1.06 | per | Sq. Foot  | 0.023    | CARP 34.55 \$/hr | 1.000      | RM10406610 |   |