

## Acoustical Testing Laboratory



TESTING
NVLAP LAB CODE 200291-0
Accredited by the National Voluntary
Laboratory Accreditation Program for
the specific scope of accreditation.

Page 1 of 5

### **TEST REPORT**

for CONFIDENTIAL OEM ON BEHALF OF DIVINE FLOORING

### **Impact Sound Transmission Test**

ASTM E 492 – 09 (2016)e1 / ASTM E 989 – 18

On

6 Inch (152 mm) Concrete Slab Floor- Ceiling Assembly
Overlaid with Loose Lay 7" x 48" 5.0mm x 0.5mm flooring
With a Suspended-Gypsum Board Ceiling
With 3-1/2 Inch Fiberglass Insulation

Report Number: NGC 7020120

Assignment Number: G-1695

Test Date: 07/29/2020

Report Reissue Date: 10/16/2020

/

Submitted by:

Anthony J. Rivers

Test Technician

Reviewed by:

Robert J. Menchetti Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.



# Acoustical Testing Laboratory



TESTING
NVLAP LAB CODE 200291-0
Accredited by the National Voluntary
Laboratory Accreditation Program for
the specific scope of accreditation.

NGC 7020120 Zhangjiagang Elegant Home-Tech Co., Ltd 10/16/2020 Page 2 of 5

### **Revision Summary:**

Date	SUMMARY
Approval Date: 10/16/2020	Original issue date: 10/16/2020
	Original NGCTS report: NGC 7020120

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.



# Acoustical Testing Laboratory



TESTING
NVLAP LAB CODE 200291-0
Accredited by the National Voluntary
Laboratory Accreditation Program for
the specific scope of accreditation.

Report Number:

NGC 7020120

Page 3 of 5

Test Method:

This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine - Designation: E 492-09 (2016)e1 / E 989-18.

The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of ASTM E 492-09 (2016)e1.

Specimen Description:

6 inch concrete slab floor suspended ceiling assembly overlaid with, according to client, Loose Lay 7" X 48" 5.0mm x 0.5mm flooring with 3-1/2 inches of fiberglass insulation.

The test specimen was a floor assembly and was observed to consist of the following: All weights and dimension are averaged:

- 1 layer of, according to the client, Loose Lay 7" X 48" 5.0mm x 0.5mm flooring. The flooring was floating on the concrete slab. Measured average thickness: 5.08 mm (0.20 in.). Measured average weight: 9.71 kg/m<sup>2</sup> (1.99 PSF)
- 152.4 mm (6 in.) thick reinforced concrete slab, weighing: 366.2 kg/m<sup>2</sup> (75.00 PSF)
- 1 layer of, 88.9 mm (3-1/2 in.) unfaced fiberglass batt insulation which was laid over the suspended grid system parallel to the main tees. Sample weight: 0.78 kg/m<sup>2</sup> (0.16 PSF)
- Gypsum wallboard ceiling grid suspension system. System is comprised of main tees and cross tees. The main tees were placed 1219.2 mm (48 in.) o.c. and the cross tees were placed 609.6 mm (24 in.) o.c. 16 gauge galvanized tie wire was used to attach the main tees to concrete anchors, located 1219.2 mm (48 in.) o.c. along the longitudinal axis, suspending the grid 304.8 mm (12 in.) below the concrete slab.
- 1 layer of, 15.9 mm (5/8 in.) Type X gypsum wallboard. The wallboard was attached parallel to the suspended grid suspension system mains, using 28.6 mm (1-1/8 in.) Type S drywall screws spaced 304.8 mm (12 in.) o.c. The wallboard joints were taped. Suspended gypsum wallboard grid ceiling weighed: 11.23 kg/m² (2.30 PSF)

The overall weight of the test assembly is: 387.87 kg/m<sup>2</sup> (79.45 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough.

The test frame was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Conditioning: Concrete slab cured for a minimum of 28 days.

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.



# Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation.

Test Report: NGC7020120 Specimen Size [m²]: 17.8			Page 4 of 5 Date: 7/29/2020				
Source room					Receiving roo	om	
					Volume [m³]:	124	
Rm Temp [°C]: 25					Rm Temp [°C]	: 25	
Humidity [%]: 50					Humidity [%]:	ty [%]: 50	
mpact Insula	tion Class IIC	[dB]:	63				
Sum of Unfavorab	le Deviations [dB]:	12					
Max. Unfavorable	Deviation [dB]:	8	at	2500	Hz		
Frequency	Ln	L2	d	Corr.	u.Dev.	ΔLn	
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]		
80	55	55.3	31.03	-0.3		2.32	
100	49	49.5	23.98	-0.5		2.48	
125	51	54.9	18.42	-3.9	2	1.73	
160	49	52.3	15.08	-3.3		1.04	
200	48	50.8	14.44	-2.8		0.70	
250	46	48.9	16.29	-2.9		0.85	
315	46	48.6	15.30	-2.6		0.40	
400	44	46.2	16.26	-2.2		0.33	
500	41	43.3	17.04	-2.3		0.37	
630	39	41.6	18.04	-2.6		0.31	
800	34	36.3	18.56	-2.3		0.38	
	32	34.6	18.11	-2.6		0.38	
1000	33	34.6	19.10	-1.6		0.26	
1000 1250				- 1		0.39	
1250 1600	33	35.1	20.52	-2.1		0.00	
1250 1600 2000	37	37.6	24.13	-0.6	2	0.23	
1250 1600 2000 2500	37 40	37.6 40.9	24.13 26.47	-0.6 -0.9	2 8	1	
1250 1600 2000 2500 3150	37 40 27	37.6 40.9 28.0	24.13 26.47 27.74	-0.6 -0.9 -1.0		0.23	
1250 1600 2000 2500	37 40	37.6 40.9	24.13 26.47	-0.6 -0.9		0.23 0.20	

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

1650 Military Road • Buffalo, NY 14217-1198 (716) 873-9750 • Fax (716) 873-9753 • www.ngctestingservices.com



# Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation.

#### Normalized impact sound pressure level


Test: ASTM E 492 - 09 (2016) / ASTM E 989 - 18

Page 5 of 5

Test Report: NGC7020120 Test Date: 7/29/2020 Specimen Size [m²]: 17.8

#### Impact Insulation Class IIC [dB]: 63

Frequency	Ln
[Hz]	[dB]
80	55
100	49
125	51
160	49
200	48
250	46
315	46
400	44
500	41
630	39
800	34
1000	32
1250	33
1600	33
2000	37
2500	40
3150	27
4000	20
5000	14



Due to high insulating value of specimen, background levels limit results at these frequencies.

= Normalized Sound Pressure Level, dB

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

> 1650 Military Road • Buffalo, NY 14217-1198 (716) 873-9750 • Fax (716) 873-9753 • www.ngctestingservices.com