

DYNA **\$STAGE®**

Model 40 30 20



Dynastage model 40 30 20 in downtown Montreal during the annual Divers/Cité festival



Dynastage model 40 30 20 can handle a full complement of sound and lighting equipment.

Contents

Technical specifications	Page 1
Rigging plan	Page 2
Side view	Page 3
Front view	Page 4
Stage floor	Page 5



Trailer

8'-2" Width 43'-8" Length 13'-6" Height Nominal gross vehicle weight 31 560 lbs Static load on axles 21 040 lbs Additional weight allowed 26 960 lbs** 7'-10" x 7'-0" x 40'-0" (2 194 ft³) Cargo space

Overall dimensions (stage)

26'-10" (32'-10" incl. FOH) Depth 43'-8 (61'-8" with PA wings) Width 27'-3" to 29'-3" (30'-3" with blocks) Height

Stage dimensions

Floor dimensions	40'-0" x 3	0'-0"	
Ground to floor height	5'-0" to 7'-0Suppport		
750" (8'-0" with blocks)		A TOWN TOWN TOWN	
Clearance under trussing	19'-9"	THEOR . ENGLA	
Clearance under roof	21'-6"	Mr. He.	

Other specifications

Floor materials Plywood over steel Load bearing capacity of the floor 150 lb per square foot

Roof materials

Front of house (FOH) supports dimensions

PA wings dimensions

Hanging pipes

Fiberglass bonded to steel structure

6'-0" 9'-0"

Six (6) industry-standard 2" nominal diameter

Maximum load bearing: Roof 20 000 lbs * Maximum load bearing: FOH supports 750 lbs * Maximum load bearing: Inside supports 500 lbs * Maximum load bearing: PA wings 1 000 lbs * Maximum load bearing: Center trusses 4 800 lbs * Maximum load bearing: Edge trusses 4 200 lbs *

Wind resistance Wind lift resistance

Motor Install time Transport Wind screen (sides and back) Wind screen openings (doors) Wind screen openings (wind flaps)

Stage skirt

Stairs

50 m/h / 80 km/h with wind screens

15 lbs per square foot

6.5 HP fuel powered Honda GX200 2 to 3 hours with 2 technicians Regular tractor-trailer

16 oz. black Vinagard

Two 7'x10'in the back and two - 4'x10'sides

Four - 6'x 3' Black Novathene TG 36" wide


Refer to rigging plan Estimated

All dimensions and specifications are subject to change without prior notice


H.P. ODULINSKI


RIGGING PLAN Model 40 30 20

MEGA STAGE






















DYNA \$STAGE®

Model 40 30 20

Specifications subject to change without prior notice ©2005 Mega-Stage



Wind Restrictions and Operating Plan

Valid for the following stages Models:

DYNA-STAGE: 24X20X14, 24X20X15 MKII, 32X24X15, 40X30X20, 40X34X20, 50X30X20.

Personnel

This stage must be supervised by a Mega-Stage Certified technician at all time during operations

during night and day off. Technician must be reachable and available in a 15 Minute time laps in case of emergency

Monitoring System:

- of the installation. (security agent during day off and night and after hours) - A competent, responsible person from Client will be present on site for the whole of the period
- ascertain if any significant weather events are expected in the immediate vicinity of the roof - A regular liaison with the local airports and weather information centers will be maintained to

Wind resistance with wind screens:

80km/h or 50mph Steady wind

120km/h or 75mph 3 second wind gust (superior to ESTA ANSI E1.21-2006 regulation)

Wind resistance without wind screens:

160km/h or 100mph

240km/h or 151 mph 3 second wind gust





Operations Management Plan:

-Side doors and back doors must be open at 65km/h or 40mph 3 second wind gust

LED screens to be lowered at 65km/h or 40mph 3 second wind gust

restrained -Sound cabinets to be lowered to stage level at 80km/h50 mph, 3 sec gust and laterally

-Scrims on sound wings to be removed at 80km/h or 50 mph, 3 sec gust

50 mph are expected, this should be done prior to these conditions for the safety of the crew. -Scrim or back drop and side walls to be open and tie to columns if winds gust over 80km/h or

-If time is allowed stage must be bring down and closed if 100 km/h gust is excepted

Level of alert vs actions

the 3 second wind speed gusts approach the following speeds against a background of rising wind speeds The following actions will be undertaken by Client personnel (8 to 12 technicians) on site when


Personnel to be on alert Level 1: 60% of design wind load

Level 2: 80% of design wind load

Personnel to be put on standby to take action

Level 3: 100% of design wind load

Personnel take action



Henryk Odulinski P.E.

641, des Loisirs, St-Eugene, Québec JOC 1J0 Tél : (819) 396-1323, e-mail :hen.o@infoteck.dr.qc.ca

St-Eugène, August 22nd 2009.

Mega-Stage 146 156 Canada Inc 927 Gaudette Street St-Jean-sur-Richelieu Québec Canada J3B 7S7

Subject: Stage Model DYNA-STAGE 40X30X20 Unit # 137

Conformity Certificate

conform to the plans and specifications and the requirements of material and workmanship in stage, this is to certify that is has been satisfactorily established that the completed works accordance with CAN-S1694M and W52.2 CSA Standard. Following the inspection and load test of completed structure of above mentioned

