

## **CETOP 5 Manifold**


## **Features:**


- Cast Iron Construction Phosphated
- 345 Bar Maximum Working Pressure
- 70 L/Min Maximum Flow Rate
- P and T Ports 3/4" BSP
- A and B Ports 1/2" BSP


## **Benefits:**

- · Reduced Fitting and Installation Costs
- · Compact design of valve circuits
- Reduces leak Paths
- · Allows for easy modification to valve assembly stacks









Part Number	No. Stations
CM5-1G	1
CM5-2G	2
CM5-3G	3
CM5-4G	4
CM5-5G	5
CM5-6G	6