CASE STUDIES

Baycrest On The Rise, Coquitlam, BC: Stormwater Management



The project began with EcoBloc Maxx base plates laid at the base of the site bed and secured with connector pieces. Blocks were then stacked and connected up to five layers and finished further endplates and pipe connections. Pipe adapters were used to secure the pipe connections in place. The structure was then wrapped with 8 oz. geotextile and an inspection port was secured. Finally, the site was backfilled evenly with gravel.

Project Team

Supplier: BARR Plastics Contractor: Gemco Construction Ltd Engineer: WSP


Specifications

Volume: 60.01 m³ **Loading:** No Vehicle **Application:** Infiltration

BARR Product

EcoBloc Maxx









1.800.665.4499 barrplastics.com