

MODEL : MSP-300-24

### OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 150 mVp-p (Max)	I/P: 230VAC O/P:FULL LOAD Ta:25°C	V1: 61.2 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 21.6 V~ 28.8 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	20.27 V~ 30.14 V/ 230 VAC 20.25 V~ 30.13 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: 1 %~ -1 % (Max)	I/P: 100 VAC / 264 VAC O/P:FULL/ MIN LOAD Ta:25°C	V1: 0.26 %~ -0.26 %	P
4	LINE REGULATION	V1: 0.2%~ -0.2 % (Max)	I/P: 100 VAC ~ 264 VAC O/P:FULL LOAD Ta:25°C	V1: 0.05 %~ -0.05 %	P
5	LOAD REGULATION	V1: 0.5 %~ -0.5 % (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: 0.26 %~ -0.26 %	P
6	SET UP TIME	230VAC: 1000 ms (Max) 115 VAC: 2500 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 152 ms 115VAC/ 350 ms	P
7	RISE TIME	230VAC: 50 ms (Max) 115VAC: 50 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 8.3 ms 115VAC/ 8.3 ms	P
8	HOLD UP TIME	230VAC: 16 ms (TYP) 115VAC: 16 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 33 ms 115VAC/ 21 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: < 5 %	P
10	DYNAMIC LOAD	V1: 2400 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	573 mVp-p	P

## INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85VAC~264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	73 V~264V	P
			I/P: LOW-LINE-3V= 97 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 100 VAC ~ 264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP)	I/P: 230 VAC	PF= 0.981 / 230 VAC	P
		0.99 / 115 VAC(TYP)	I/P: 115 VAC O/P:FULL LOAD Ta:25°C	PF= 1 / 115 VAC	
4	EFFICIENCY	87% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	87.3 %	P
5	INPUT CURRENT	230V/ 2.5 A (TYP)	I/P: 230 VAC	I = 1.7 A/ 230 VAC	P
		115V/ 4.5 A (TYP)	I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 3.45 A/ 115 VAC	
6	INRUSH CURRENT	230V/ 70 A (TYP)	I/P: 230 VAC	I = 68 A/ 230 VAC	P
		115V/ 35 A (TYP) COLD START	I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 34 A/ 115 VAC	
7	LEAKAGE CURRENT	< 450 uA / Earth	I/P: 264 VAC O/P:Min LOAD Ta:25°C	L-FG 420 uA	P
		< 100 uA / Touch		N-FG 420 uA	
		L-V+ 94 uA			
		L-V- 94 uA			
		N-V+ 94 uA			
		N-V- 94 uA			

## PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 %~ 135 %	I/P: 230 VAC I/P: 115 VAC O/P: TESTING Ta: 25°C	117% / 230 VAC 117% / 115 VAC Constant current limiting, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	CH1: 30V~ 34.8V	I/P: 230 VAC I/P: 115 VAC O/P: MIN LOAD Ta: 25°C	32.53 V / 230 VAC 32.52 V / 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC: TSW1: 90 ± 5°C detect on heatsink of power transistor TSW2: 95 ± 5°C detect on O/P CHOCK NO DAMAGE	I/P: 230 VAC O/P: FULL LOAD	O.T.P. Active Shut down o/p voltage, recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta: 25°C	NO DAMAGE Constant current limiting, recovers automatically after fault condition is removed	P

## CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	DC OK SIGNAL	PSU turn on : 3.3 ~ 5.6V ; PSU turn off : 0 ~ 1V	I/P: 230 VAC O/P: FULL LOAD Ta: 25°C	PSU turn on : 5.213 V PSU turn off : 0 V	P
2	REMOTE CONTROL	Rc+ / Rc- 4 ~ 10V or open = power on 0 ~ 0.8V or short = power off	I/P: 230 VAC O/P: FULL LOAD Ta: 25°C	3V ~ 10 V POWER ON 0V ~ 2.9 V POWER OFF	P
3	REMOTE SENSE	>0.5V	I/P: 230 VAC O/P: FULL LOAD Ta: 25°C	>0.5	P
4	AUX POWER	4.75V~5.25V / 0.3A Ripple: 50mV	I/P: 230 VAC O/P: FULL LOAD Ta: 25°C	4.904V/0.3A Ripple: 16 mV	P
5	No load power consumption	<0.5W	I/P: 240 VAC O/P: NO LOAD RC+&RC- SHORT Ta: 25°C	0.4W	P
6	FAN ON/OFF control test	LOAD 35±15% OR RTH2 >= 50°C FAN ON	I/P: 230 VAC O/P: TESTING Ta: 25°C	> 29.6 %LOAD FAN ON < 29.5 %LOAD FAN OFF	P

## ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : MSP-300-24 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 31.8 °C 2. HIGH AMBIENT BURN-IN : 5.5 HRS I/P : 230VAC O/P : FULL LOAD Ta= 52.9 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )	I/P : 230 VAC O/P : 111 % LOAD Ta : 25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 230 VAC O/P : 100 % LOAD Ta= -30 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 49.9 °C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.03 % (0-50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.017 % (0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set (1) Waveform: Sine Wave (2) Frequency: 10-500Hz (3) Sweep Time: 10min/sweep cycle (4) Acceleration: 5G (5) Test Time: 1 hour in each axis (X.Y.Z) (6) Ta: 25°C		TEST : OK	P

### SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 4 KVAC/min I/P-FG: 2 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 4.2KVAC/min I/P-FG: 2.4KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 2.581 mA I/P-FG: 1.991 mA O/P-FG: 0.947 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C / 70%RH	I/P-O/P: 30 GΩ I/P-FG: 19.1 GΩ O/P-FG: 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta:25°C / 70%RH	13 mΩ	P

### E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS D	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55011 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55011 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:6KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

### M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	MSP-300-24:SUPPOSE C106 IS THE MOST CRITICAL COMPONENT	I/P : 230VAC O/P : FULL LOAD Ta= 25 °C I/P : 230VAC O/P : FULL LOAD Ta= 50 °C	LIFE TIME= 2632336.2 HRS LIFE TIME= 410763.6 HRS	P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 176K HRS			P



## COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) <b>Peak Voltage</b>	Q4 Rated 2SK4106 : 12A/500V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Output Short Ta:25°C	(1) 472 V (2) 438 V	P
2	Diode Peak <b>Voltage</b>	Q101 Rated FME-220B : 20A/150V  Q104 Rated FME-220B : 20A/150V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2)Output Short Ta:25°C	(1) 150 V (2) 138 V  (1) 149 V (2) 146 V	P
3	<b>Input Capacitor Voltage</b>	C5 Rated 100u/400V 105°C PEAK 450V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 369.9 V (2) 374 V (3) 371.9 V	P
4	<b>Control IC Voltage Test</b>	U1 Rated FAN4801NY:9.3V~ 30V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 15.917 V (2) 13.371 V (3) 13.371 V	P
5	P.F.C Transistor (D to S) or (C to E) <b>Peak Voltage</b>	Q1 Rated IRFP460A :20A/500V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Output Short Ta:25°C	(1) 494 V (2) 392 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2012/3/15	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023