


MOBIFENCE™ INSTALLATION DATA SHEET

Required material

Mobi-Fence™ fabric:

Delivered in rolls $164' \times 39'' (50 \times 1 \text{ m})$ with included channels 4'' (100 mm) diameter in order to insert stakes of fixation.

Approximate weight of a roll: 44 lb (20 Kg)



For channels 4" (100 mm) diam, stakes 3.15" (80 mm) diam and 60" (1.50 m) high For channels 6" (150 mm) diam, stakes 4.72" (120 mm) diam and 120" (2.00 m) high

Material for cutting:

Hot cut or soldering iron in order to avoid raveling (please cut at about 4" (100 mm) from the channels)

Setting material:

Digger to push in the stakes, sand spade

People:

It is better to be 2 people

Installation

Prepare the Mobi-Fence^m at the expected length (cauterize the fabric with a soldering iron in order to avoid the raveling) (*Picture 1*).

Be careful: Check that the wooden stakes, when digging in, do not ravel the fabric (sliver of wood). If raveled, melt the fabric with a soldering iron.

Prepare the ground by digging a drainage channel of about 4" x 4" (100 x 100 mm).

Unroll the Mobi-Fence™.

Insert the 1st stake in the 1st channel (*Picture 2*).

Raise the set and dig in the 1st stake (Picture 3).

Insert the 2nd stake in the 2nd channel (*Picture 4*).

Stretch the fabric at the maximum.

Dig in the 2nd stake.

After positioning the all length, add some sand at the bottom of the fabric, around 8" (20 cm), in order to avoid the wind rushing under the fabric and making a hole (*Picture 5*).





