


AREA LIGHT BRACKETS - 3" REDUCED DRILL PATTERN (XASU/XAMU/PASU/XLCS/XLCM)

BOLT ON BRACKETS (with 3" Reduced Drill Pattern)

EXTENSION ARM - Use this 6" extension arm to position the fixture further from the pole.

BKA-XBO-EC-6-CLR

Note: PASU/XASU/XAMU can be mounted in any drilling configuration (D180, D90, etc.) without the use of this arm. Order Number 382136CLR



ROUND POLE PLATE - For mounting fixtures to round poles




X4RPP - For 4" Round Poles
X5RPP - For 5" Round Poles

Order Number
379967CLR
379968CLR

WALL MOUNT PLATE - Order Number 382132CLR


BKS XBO WM * CLR

8" x 8"
(203mm x 203mm)



TENON BRACKETS (with 3" Reduced Drill Pattern)


BKA-XNM-* -CLR - Tenon mount fitter slip-fits 2-3/8" O.D. tenon (2.0 pipe tenon).



BKA-XNM-S or D180-* -CLR
Single/D180
(Drilled 2 Sides)

BKA-XNM-D90, T90 or Q90-* -CLR
D90/T90/Q90
(Drilled 4 Sides)

INTERNAL SLIP-FITTER - Fits 4" (102mm) or 5" (127mm) SQI square steel poles with wall thickness of 11ga. (0.120"-3mm) or 7ga. (0.180"-5mm)




BKA-X4ISF-D180-* -CLR
BKA-X4ISF-Q90-* -CLR
BKA-X5ISF-D180-* -CLR
BKA-X5ISF-Q90-* -CLR


RETROFIT BRACKETS - Mounting adaptor plates convert poles with existing 2-, 3-, and 4-hole LSI drilling patterns to use with fixtures with 3" reduced drill pattern.

BKS-XBO-ADP-2H-CLR - To convert 2-hole 5" traditional LSI drilling pattern used with Challenger, Greenbriar, etc. on round or square poles. Order Number 388239CLR

BKS-XBO-ADP-2H-CLR
5-9/16" x 2-5/8"



BKS-XBO-ADP-2H-CLR-EC6
Mounting Bracket w/EC6 Arm



BKS-XBO-ADP-3H-CLR
4-1/2" x 3-3/4"



BKS-XBO-ADP-4H-CLR
4-3/4" x 3-3/4"



BKS-XBO-ADP-2H-CLR-EC6 - To convert 2-hole 5" traditional LSI drilling pattern and with 6" extension arm and proper hardware for use with round or square poles. Order Number 388241CLR

BKS-XBO-ADP-3H-CLR¹ - To convert 3-hole LSI drilling pattern on square poles. Order Number 388059CLR

BKS-XBO-ADP-4H-CLR¹ - To convert 4-hole LSI drilling pattern on square poles. Order Number 388060CLR

FOOTNOTES:

1- When ordering adaptors for 3- and 4-hole drilled square poles, ordering a replacement cap is also recommended due to the aging of the existing plastic pole cap.

ARRA
Funding Compliant



Project Name _____ Fixture Type _____
Catalog # _____

03/20/15
© 2015
LSI INDUSTRIES INC.

AREA LIGHT BRACKETS - 3" REDUCED DRILL PATTERN (XASU/XAMU/PASU/XLCS/XLCM)

BRACKET ORDERING INFORMATION

Bracket Designation ¹	Bracket Type	Bracket Configuration	Length	Bracket Finish	Options	EPA Values ²	Estimated Weight (kg/lbs.)			
BKA – Bracket Aluminum	XBO-Bolt-On	EC - Extension	6"	BRZ – Bronze BLK – Black PLP – Platinum Plus WHT – White GPT - Graphite SVG - Satin Verde Green MSV - Metallic Silver	None	0.5	2/5			
	XNM-Tenon Mount	S - Single D180°-Double D90°-Double T90°-Triple Q90°-Quad	*			0.5	3/6			
						0.5	3/6			
						0.5	3/6			
						0.5	3/6			
						0.5	3/6			
	X4ISF-Internal Fitter	D180°-Double Q90°-Quad	*			0.4	3/7			
						0.4	3/7			
	X5ISF-Internal Fitter	D180°-Double Q90°-Quad	*			0.5	4/9			
						0.5	4/9			
	BKS – Bracket Steel	XBO-Bolt-On	WM-Wall Mount			*			-	2/5
		XBO-ADP-Pole Retrofit Bracket	2H - 2 Hole			*			-	1/2
2H - 2 Hole				*	0.3				3/7	
			3H - 3 Hole 4H - 4 Hole		*	EC6 - w/extension arm			-	1/2
None				-					1/2	

FOOTNOTES:

1- For mounting of fixtures with 3" reduced drilling pattern.

2- The bracket EPA should be added to the fixture EPA when selecting the proper pole.

